

ESTIMATION DPR							
State	Odisha	District	Balasore	Block	Basta	Gram Panchayat	Natakata

Work Code	OD/346/3301/116130/392348/00064184 (IMPROVEMENT OF ROAD FROM BASANTAPUR CHHAK ROAD ADIVASI SAHI TO RABINDRA DEY HOUSE WITH GUARDWALL)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Basta	Proposal Date	08-06-2021
Date of Commencement	17-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	BHAGYALAXMI MOHANTA		

Administrative Approval Details

Approval No.	OD/346/3301/116130/392348/00064184/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3301/116130/392348/00064184/TS
Fund Sanction No.	9122
Fund Sanction Amount (in Rs.)	254824

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Road Work (AR1307) ∴.Supplying & spreading moorum and consolidation with HRR - Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.	-	83.36359732	Cum
i)	BRM025 : Gravel or moorum	1.28	106.7054045696	1 Cum

2	<p>Special items for irrigation works(AR0216) .Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. - Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.</p>	-	497.809344	Cum
i)	<p>BRMMR0065 : Add for trimming of slope and bed manually.</p>	1	497.809344	L.S.
ii)	<p>BRMMR0102 : Cost of mechanical excavation per cum without supervision charge for item AR0216</p>	1	497.809344	Cum
iii)	<p>BRMMR0104 : ost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216</p>	1	497.809344	Cum

3	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	8.1552384	Cum
4	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	1.345614336	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	1.345614336	1 Cum
5	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	8.576592384	Cum
i)	<p>BRM340 : Cement</p>	2.29	19.64039655936	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.48	4.11676434432	1 Cum

iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	8.23352868864	1 Cum.
6	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	23.72371008	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0633423059136	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.98918747008	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM025	106.7054045696	1 Cum	862.69	92053.685468148
2	BRMMR0065	497.809344	L.S.	1	497.809344
3	BRMMR0102	497.809344	Cum	25.01	12450.21169344
4	BRMMR0104	497.809344	Cum	40.49	20156.30033856
5	BRM029	1.345614336	1 Cum	738.55	993.8034678528
6	BRM340	19.64039655936	1 Qntl.	570.467	11204.198104028
7	BRM028	4.11676434432	1 Cum	743.49	3060.7731223585
8	BRM044	8.23352868864	1 Cum.	2289.56	18851.157944363
9	BRM104	0.0633423059136	1Cum.	58573.086	3710.1543317156
10	BRM092	2.98918747008	1Mtr.	229.106	684.84078452015

Total: 163662.93459899