

ESTIMATION DPR							
State	Odisha	District	Balangir	Block	Belpara	Gram Panchayat	Parlimal

Work Code	OD/345/3287/115838/420929/00061908 (CONST OF CC ROAD AT MUNAPALI UPPERPADA)						
Project Category	Road						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Belpara	Proposal Date	11-12-2024
Date of Commencement	03-11-2025	Date of Completion	14-11-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	JAGUNA NANDA SAMARTHA		

Administrative Approval Details

Approval No.	OD/345/3287/115838/420929/00061908/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/345/3287/115838/420929/00061908/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	200000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0101a) ∴Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift - Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	4.7081	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	11.7035	Cum
i)	BRM029 : Sand for filling and road blinding	1	11.7035	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	18.9481	Cum
i)	BRM340 : Cement	2.29	43.391149	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	9.095088	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	18.190176	1 Cum.

4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	12.21525	Cum
i)	BRM340 : Cement	3.23	39.4552575	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.4968625	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	10.993725	1 Cum.
5	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	20.47	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0546549	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.57922	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	11.7035	1 Cum	487.264	5702.694224
2	BRM340	82.8464065	1 Qntl.	572.0931	47395.857518445
3	BRM028	14.5919505	1 Cum	492.204	7182.216403902
4	BRM044	18.190176	1 Cum.	1410.574	25658.589321024
5	BRM056	10.993725	1 Cum.	1811.944	19920.0140514
6	BRM104	0.0546549	1Cum.	58619.6948	3203.8535573245
7	BRM092	2.57922	1Mtr.	275.7148	711.129126456
					Total: 109774.35420255