

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Patana	Gram Panchayat	Rajanagar

Work Code	OD/361/3453/119489/385723/00047796 (CONST. OF CC ROAD AT DAMA SAHI RAJNAGAR)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Patana	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	Chief Minister Special Assistant	Scheme Component Name	Special Problem Fund (SPF) 16 th Phase
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
--------------	--

Technical Sanction Details

Technical Sanction No.	OD/361/3453/119489/385723/00047796/TS
Fund Sanction No.	4229
Fund Sanction Amount (in Rs.)	300000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0122Aia) ∴Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift - Earthwork in all kinds of soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	-	27.28	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	11.315	Cum
i)	BRM029 : Sand for filling and road blinding	1	11.315	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	28.83	Cum
i)	BRM340 : Cement	2.29	66.0207	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	13.8384	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	27.6768	1 Cum.

4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	17.6514	Cum
i)	BRM340 : Cement	3.23	57.014022	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.94313	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	15.88626	1 Cum.
5	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	24.8	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.066216	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	3.1248	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	11.315	1 Cum	526.31	5955.19765
2	BRM340	123.034722	1 Qntl.	610.142	75068.651350524
3	BRM028	21.78153	1 Cum	536.31	11681.6523543
4	BRM045	27.6768	1 Cum.	1221.31	33801.952608
5	BRM056	15.88626	1 Cum.	1841.31	29251.5294006
6	BRM104	0.066216	1Cum.	58715.766	3887.923161456
7	BRM092	3.1248	1Mtr.	371.786	1161.7568928
					Total: 160808.66341768