

ESTIMATION DPR							
State	Odisha	District	Kalahandi	Block	Thuamul Rampur	Gram Panchayat	Gopalpur

Work Code	OD/358/3421/118853/424417/00052289 (CONST. OF CC ROAD FROM RD ROAD TO BHATAGUDA NAIK PADA)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Thuamul Rampur	Proposal Date	-
Date of Commencement	10-04-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	PRATAP KUMAR SAHOO		

Administrative Approval Details

Approval No.	OD/358/3421/118853/424417/00052289/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/358/3421/118853/424417/00052289/TS
Fund Sanction No.	1752
Fund Sanction Amount (in Rs.)	300000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	5.04	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.35625	Cum
i)	BRM029 : Sand for filling and road blinding	1	15.35625	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	28.035	Cum
i)	BRM340 : Cement	2.29	64.20015	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	13.4568	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	26.9136	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	17.24625	Cum
i)	BRM340 : Cement	3.23	55.7053875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.7608125	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	15.521625	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	25.2	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.067284	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	3.1752	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	15.35625	1 Cum	347.95	5343.2071875
2	BRM340	119.9055375	1 Qntl.	626.392	75107.8694457
3	BRM028	21.2176125	1 Cum	704.43	14946.322773375
4	BRM045	26.9136	1 Cum.	1193.57	32123.265552
5	BRM056	15.521625	1 Cum.	2304.53	35770.05046125
6	BRM104	0.067284	1Cum.	58810.886	3957.031653624
7	BRM092	3.1752	1Mtr.	229.106	727.4573712
					Total: 167975.20444465