

ESTIMATION DPR							
State	Odisha	District	Angul	Block	Kishorenagar	Gram Panchayat	Dhadarpal

Work Code	OD/344/3281/115695/404693/00079308 (Construction of Market Complex near GP Office, Dhadarpal)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Kishorenagar	Proposal Date	-
Date of Commencement	24-02-2026	Date of Completion	14-03-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	MANORANJAN PRADHAN		

Administrative Approval Details

Approval No.	OD/344/3281/115695/404693/00079308/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/344/3281/115695/404693/00079308/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	29.7144	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	64.43364	Cum
i)	BRM029 : Sand for filling and road blinding	1	64.43364	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.85436	Cum
i)	BRM340 : Cement	2.29	20.2764844	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.2500928	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	8.5001856	1 Cum.

4	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	27.530886	Cum
i)	BRM340 : Cement	0.672	18.500755392	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	7.70864808	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	9635.8101	1000 Nos
5	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	23.129475	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	23.129475	1 Cum
ii)	BRM340 : Cement	0.672	15.5430072	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	6.476253	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	8095.31625	1000 Nos
6	R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	26.49121	Cum
i)	BRM340 : Cement	3.4733	92.011919693	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	11.9210445	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	9.5368356	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	14.3052534	1 Cum.
7	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	78.103	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.20853501	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	9.840978	1Mtr.
8	R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	15.831	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	4.2621923076923	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.083823115384615	1Cum.

9	R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm	-	35.917	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	19.839866666667	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.186426333333333	1Cum.
10	R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	68.5926	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	42.67984	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.34448728	1Cum.

11	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	26.5	Qntl
i)	BRM162 : Binding Wire.	0.8	21.2	1 Kg.
ii)	BRM341 : Steel	1.05	27.825	1 Qntl.
12	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	162.545	Sqm
i)	BRM340 : Cement	0.0358	5.819111	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	2.438175	1 Cum

13	Plastering (AR1014) ::16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	143.4262	Sqm
i)	BRM340 : Cement	0.043	6.1673266	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.5816716	1 Cum
14	Flooring (AR0802i) ::2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	39.04	Sqm
i)	BRM340 : Cement	0.0858	3.349632	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.46848	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	0.89792	1 Cum.

15	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-		143.426	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084		12.047784	1 Ltr
16	Painting(AR0918cb) :.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-		143.426	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125		17.92825	1 Ltr
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161		12.954606451613	1 Ltr
17	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-		201.585	Sqm
i)	BRM142 : Distemper	0.25		50.39625	1 Kg.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
--------	---------------	-----	------	------	--------

1	BRM029	64.43364	1 Cum	543.25	35003.57493
2	BRM340	161.668236285	1 Qntl.	551.372	89139.338776933
3	BRM028	35.84436498	1 Cum	873.69	31316.863239376
4	BRM044	8.5001856	1 Cum.	1792.06	15232.842606336
5	BRM005	17731.12635	1000 Nos	6.4606	114553.71489681
6	BRMMR0025	23.129475	1 Cum	33	763.272675
7	BRM060	9.5368356	1 Cum.	2202.03	21000.398096268
8	BRM052	14.3052534	1 Cum.	2179.1	31172.57768394
9	BRM104	0.82327173871795	1Cum.	58620.646	48260.721157189
10	BRM092	9.840978	1Mtr.	276.666	2722.664019348
11	BRM094	4.2621923076923	1Mtr.	287.666	1226.0878123846
12	BRM084	62.519706666667	1Mtr	297.726	18613.74218704
13	BRM162	21.2	1 Kg.	90.1	1910.12
14	BRM341	27.825	1 Qntl.	6386.662	177708.87015
15	BRM056	0.89792	1 Cum.	2193.43	1969.5246656
16	BRM253	25.002390451613	1 Ltr	159.33732	3983.8138881536
17	BRM255	17.92825	1 Ltr	195.09732	3497.75352729
18	BRM142	50.39625	1 Kg.	70.40732	3548.26490055
Total:					601624.14521222