

ESTIMATION DPR							
State	Odisha	District	Jagatsinghpur	Block	Jagatsinghpur	Gram Panchayat	Salijanga

Work Code	OD/355/3389/118139/398019/00013704 (Construction of CC Road from Jota Mallick sahi to Pradhan sahi)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Jagatsinghpur	Proposal Date	11-02-2024
Date of Commencement	20-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Tanushree Rout		

Administrative Approval Details

Approval No.	OD/355/3389/118139/398019/00013704/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/355/3389/118139/398019/00013704/TS
Fund Sanction No.	8053
Fund Sanction Amount (in Rs.)	400000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0101aa) :.Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift - Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum	-	9.521524	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	19.043048	Cum
i)	BRM029 : Sand for filling and road blinding	1	19.043048	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	32.75404256	Cum
i)	BRM340 : Cement	2.29	75.0067574624	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	15.7219404288	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	31.4438808576	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	19.043048	Cum
i)	BRM340 : Cement	3.23	61.50904504	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	8.5693716	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	17.1387432	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	53.98035912	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1441275588504	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	6.80152524912	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	19.043048	1 Cum	404.31	7699.29473688
2	BRM340	136.5158025024	1 Qntl.	603.877	82438.753267742
3	BRM028	24.2913120288	1 Cum	412.82	10027.939431729
4	BRM044	31.4438808576	1 Cum.	2262.51	71142.094879129
5	BRM056	17.1387432	1 Cum.	2708.31	46417.029595992
6	BRM104	0.1441275588504	1Cum.	58573.086	8441.9958995145
7	BRM092	6.80152524912	1Mtr.	229.106	1558.2702437249
					Total: 227725.37805471