

ESTIMATION DPR							
State	Odisha	District	Sundargarh	Block	Lahunipara	Gram Panchayat	Bhutuda

Work Code	OD/373/3582/121659/384956/00023180 (Construction Of Market Complex At Bhutuda Gp)						
Project Category	Building						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Lahunipara	Proposal Date	31-08-2024
Date of Commencement	21-11-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	PRASANTA ROUT		

Administrative Approval Details

Approval No.	OD/373/3582/121659/384956/00023180/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3582/121659/384956/00023180/TS
Fund Sanction No.	7387
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	35.352	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.9075	Cum
i)	BRM029 : Sand for filling and road blinding	1	26.9075	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.20275	Cum
i)	BRM340 : Cement	2.29	23.3642975	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.89732	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.79464	1 Cum.

4	Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	7.0928	Cum
i)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	400	2837.12	1000 Nos
ii)	BRM340 : Cement	0.672	4.7663616	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.985984	1 Cum
5	Masonry Brick Work (AR0603ci) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	20.029435	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	20.029435	1 Cum
ii)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	400	8011.774	1000 Nos
iii)	BRM340 : Cement	0.672	13.45978032	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.6082418	1 Cum
6	R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	25.839815	Cum
i)	BRM340 : Cement	3.4733	89.7494294395	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	11.62791675	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	9.3023334	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	13.9535001	1 Cum.
7	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	25.83	Qntl
i)	BRM162 : Binding Wire.	0.8	20.664	1 Kg.
ii)	BRM341 : Steel	1.05	27.1215	1 Qntl.
8	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	32.64	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0871488	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.11264	1Mtr.

9	R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	10.56	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	2.8430769230769	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.055913846153846	1Cum.
10	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	56.4225	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.62222222222222	35.1073333333333	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.283366333333333	1Cum.

11	R.C.C. Work (AR0410d) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm	-	40.58	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	22.415619047619	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.21062952380952	1Cum.
12	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	103.626	Sqm
i)	BRM340 : Cement	0.0358	3.7098108	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.55439	1 Cum

13	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	107.175	Sqm
i)	BRM340 : Cement	0.043	4.608525	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.92915	1 Cum
14	Plastering (AR1026) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces (inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	51.0225	Sqm
i)	BRM340 : Cement	0.0271	1.38270975	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.38266875	1 Cum
15	Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	48.5025	Sqm
i)	BRM340 : Cement	0.0858	4.1615145	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.58203	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1.1155575	1 Cum.
16	Concrete (AR0317) : 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge. (new work)	-	48.96	Sqm
i)	BRM340 : Cement	0.1208	5.914368	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0169	0.827424	1 Cum
iii)	BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	0.827424	1 Cum.
17	Painting(AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	261.8	Sqm

i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	21.9912	1 Ltr
18	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	158.2	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	19.775	1 Litre
19	Painting(AR0918f) :.Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside) - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	103.626	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	12.95325	1 Ltr
20	miscellaneous(ARM105) :.Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.	-	15.435	Sqm

i)	BRMM105 : Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works)	1	15.435	Sqm
21	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	3.5	Qntl
i)	BRM341 : Steel	1	3.5	1 Qntl.
22	Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	15.435	Sqm
i)	BRM137 : Red oxide Primer	0.054	0.83349	1 Litre
ii)	BRM141 : Enamel paint	0.125	1.929375	1 Litre

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	26.9075	1 Cum	738.55	19872.534125
2	BRM340	151.1167969095	1 Qntl.	606.072	91587.659336534
3	BRM028	29.3951253	1 Cum	743.49	21854.981709297
4	BRM044	9.79464	1 Cum.	2409.16	23596.8549024
5	BRM006	10848.894	1000 Nos	7.4439	80758.0820466
6	BRMMR0025	20.029435	1 Cum	33	660.971355
7	BRM060	9.3023334	1 Cum.	2803.91	26082.905643594
8	BRM052	13.9535001	1 Cum.	2796.2	39016.77697962
9	BRM162	20.664	1 Kg.	90.1	1861.8264
10	BRM341	30.6215	1 Qntl.	6715.547	205640.1224605
11	BRM104	0.6370585032967	1Cum.	58639.67	37356.900404013

12	BRM092	4.11264	1Mtr.	295.69	1216.0665216
13	BRM094	2.8430769230769	1Mtr.	306.69	871.94326153846
14	BRM084	57.522952380952	1Mtr	316.75	18220.395166667
15	BRM057	1.1155575	1 Cum.	2499.1	2787.88974825
16	BRM064	0.827424	1 Cum.	2264.11	1873.37895264
17	BRM253	21.9912	1 Ltr	159.63457	3510.555755784
18	BRM140	19.775	1 Litre	249.94457	4942.65387175
19	BRM255	12.95325	1 Ltr	195.39457	2530.9947138525
20	BRMM105	15.435	Sqm	16.22	250.3557
21	BRM137	0.83349	1 Litre	142.60457	118.8594830493
22	BRM141	1.929375	1 Litre	205.94457	397.34430474375
					Total: 585010.05284243