

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Kalahandi	<b>Block</b>	Karlamunda	<b>Gram Panchayat</b>	Karlamunda

<b>Work Code</b>	OD/358/3415/118733/422425/00038905 (RENOVATION OF ODIAMUNDA TANK AT KARLAMUNDA)
<b>Project Category</b>	Water Body

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Karlamunda	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance of Capital Assets
<b>Project Sub-Category</b>	Tank	<b>Project Type</b>	Renovation or Rejuvenation
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	1313
<b>Fund Sanction Amount (in Rs.)</b>	750000

### MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p><b>Special items for irrigation works(AR0216)</b>  <b>.Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. -</b>  Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete.  Per 1 cum.</p>	-		7360	Cum
i)	<b>BRMMR0065</b> : Add for trimming of slope and bed manually.	1		7360	L.S.
ii)	<b>BRMMR0102</b> : Cost of mechanical excavation per cum without supervision charge for item AR0216	1		7360	Cum
iii)	<b>BRMMR0104</b> : ost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216	1		7360	Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRMMR0065</b>	7360	L.S.	1	7360
2	<b>BRMMR0102</b>	7360	Cum	25.01	184073.6
3	<b>BRMMR0104</b>	7360	Cum	40.49	298006.4

**Total: 489440**