

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Biramaharajpur	Gram Panchayat	Champamal

Work Code	OD/372/3568/275228/419414/00052526 (Provision of facility Center Champamal GP HQ)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Biramaharajpur	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	33921
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	21.657424	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	32.61267096	Cum
i)	BRM029 : Sand for filling and road blinding	1	32.61267096	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.5701555616	Cum
i)	BRM340 : Cement	2.29	19.625656236064	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.113674669568	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	8.227349339136	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	5.5956824768	Cum
i)	BRM340 : Cement	3.4733	19.435483946669	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.51805711456	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.014445691648	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.021668537472	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.022410708319584	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1.0575839881152	1Mtr.

5	<p>R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)</p>	-	1.8583463284	Cum
i)	BRM340 : Cement	3.4733	6.4545943024317	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.83625584778	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.669004678224	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.003507017336	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.02480892348414	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1.170758186892	1Mtr.

6	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	4.3028747452	Cum
i)	BRM340 : Cement	3.4733	14.945174852503	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.93629363534	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.549034908272	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.323552362408	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	19.016985223886	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.17869408529341	1Cum.

7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.11948574	Cum
i)	BRM340 : Cement	3.4733	3.888309820742	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.503768583	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.4030148664	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.6045222996	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	4.21990149693	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.08299139610629	1Cum.

8	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	7.7943462668	Cum
i)	BRM340 : Cement	3.4733	27.072102888476	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.50745582006	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.805964656048	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.208946984072	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	48.493304733523	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.39141024534915	1Cum.

9	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	18	Qntl
i)	BRM162 : Binding Wire.	0.8	14.4	1 Kg.
ii)	BRM341 : Steel	1.05	18.9	1 Qntl.
10	Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	12.5806235	Cum
i)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	5032.2494	1000 Nos
ii)	BRM340 : Cement	0.672	8.454178992	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	3.52257458	1 Cum

11	<p>Masonry Brick Work (AR0603ci) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	17.28696444	Cum
i)	<p>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</p>	1	17.28696444	1 Cum
ii)	<p>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p>	400	6914.785776	1000 Nos
iii)	<p>BRM340 : Cement</p>	0.672	11.61684010368	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	4.8403500432	1 Cum
12	<p>Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	61.5927	Sqm
i)	<p>BRM340 : Cement</p>	0.0372	2.29124844	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.46194525	1 Cum
13	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	109.598775	Sqm
i)	BRM340 : Cement	0.0358	3.923636145	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.643981625	1 Cum
14	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	80.521075	Sqm
i)	BRM340 : Cement	0.043	3.462406225	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.44937935	1 Cum

15	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	49.00475	Sqm
i)	BRM174 : White Cement.	0.0076	0.3724361	1Qntl
ii)	BRM340 : Cement	0.1074	5.26311015	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	1.02909975	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	49.00475	1 Sqm.
16	<p>Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	230.51864	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	19.36356576	1 Ltr

17	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	114.11836	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	14.264795	1 Litre
18	Painting(AR0918Ai) :.Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	116.40028	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075	8.730021	1 Ltr
19	Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	18.6729	Sqm
i)	BRM137 : Red oxide Primer	0.054	1.0083366	1 Litre
ii)	BRM141 : Enamel paint	0.125	2.3341125	1 Litre

20	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	3.36675	Qntl
i)	BRM341 : Steel	1	3.36675	1 Qntl.
21	Other Building Items. (AR1902) :.cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.	-	114.12	Sqm
i)	BRMMR0038 : Cement based putty	0.8	91.296	kg

22	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	23.55015	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	23.55015	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	3.238145625	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.35325225	1 Cum

23	<p>miscellaneous(ARM29 7) :.Supplying, fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items) and as directed by Engineer-in-Charge. -</p> <p>Supplying, fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	4.4592	Sqm
i)	<p>BRMM297 : Supplying, fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items)</p>	1	4.4592	1 Sqm
24	<p>miscellaneous(ARM29 8) :.Supplying, fitting and fixing of openable UPVC doors with door frame of approved make with 6mm thick glass. - Supplying, fitting and fixing of openable UPVC doors with door frame of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	4.87725	Sqm

i)	BRMM298 : Supplying, fitting and fixing of openable UPVC doors with door frame of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items)	1	4.87725	1 Sqm
25	Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	7.0604	Sqm
i)	BRMMR0027 : Wax Polish	1	7.0604	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	7.0604	1 Sqm.
iii)	BRM340 : Cement	0.2737	1.93243148	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.0917852	1 Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	32.61267096	1 Cum	347.95	11347.578860532
2	BRM340	131.60331920757	1 Qntl.	540.227	71095.666325546

3	BRM028	26.807873718508	1 Cum	352.89	9460.2305565243
4	BRM044	8.227349339136	1 Cum.	1857.16	15279.50409867
5	BRM060	7.441464800592	1 Cum.	2280.58	16970.855794934
6	BRM052	11.162197200888	1 Cum.	2241.91	25024.641526643
7	BRM104	0.70031535855257	1Cum.	58573.086	41019.631723621
8	BRM092	2.2283421750072	1Mtr.	229.106	510.5265623472
9	BRM084	67.510289957409	1Mtr	250.166	16888.779197485
10	BRM094	4.21990149693	1Mtr.	240.106	1013.2236688219
11	BRM162	14.4	1 Kg.	90.1	1297.44
12	BRM341	22.26675	1 Qntl.	6240.747	138961.15326225
13	BRM006	11947.035176	1000 Nos	5.36398	64083.65774336
14	BRMMR0025	17.28696444	1 Cum	33	570.46982652
15	BRM174	0.3724361	1Qntl	2041.967	760.5022258087
16	BRM131	49.00475	1 Sqm.	660.6811111	32376.512679178
17	BRM253	19.36356576	1 Ltr	159.27787	3084.1875098577
18	BRM140	14.264795	1 Litre	249.58787	3560.3198000367
19	BRM255	8.730021	1 Ltr	195.03787	1702.6847008953
20	BRM137	1.0083366	1 Litre	142.94787	144.13956921304
21	BRM141	2.3341125	1 Litre	205.58787	479.86521721537
22	BRMMR0038	91.296	kg	30	2738.88
23	BRM129	23.55015	1 Sqm.	414.8011111	9768.6283865717
24	BRMM297	4.4592	1 Sqm	4960.97	22121.957424
25	BRMM298	4.87725	1 Sqm	8682.12	42344.86977
26	BRMMR0027	7.0604	1 Sqm	8.5	60.0134
27	BRM130	7.0604	1 Sqm.	459.6811111	3245.5325168104

Total: 535911.45234684