

ESTIMATION DPR							
State	Odisha	District	Dhenkanal	Block	Hindol	Gram Panchayat	Babandha

Work Code	OD/352/3352/117310/403103/00061668 (Const of Community Centre at Surat Harijan sahi)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Hindol	Proposal Date	-
Date of Commencement	20-03-2026	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	Community Centre	Project Type	New Work
Name of Executant	MUNARAM MURMU		

Administrative Approval Details

Approval No.	OD/352/3352/117310/403103/00061668/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/352/3352/117310/403103/00061668/TS
Fund Sanction No.	3850
Fund Sanction Amount (in Rs.)	364291

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.00532432	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	13.6561732352	Cum
i)	BRM029 : Sand for filling and road blinding	1	13.6561732352	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.4285620352	Cum
i)	BRM340 : Cement	2.29	5.561407060608	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	1.165709776896	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	2.331419553792	1 Cum.

4	R.C.C. Work (AR0404Aa) ∴Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	2.265344	Cum
i)	BRM340 : Cement	3.4733	7.8682193152	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.0194048	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.81552384	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.22328576	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.00907270272	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.428150016	1Mtr.

5	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	0.9035847838464	Cum
i)	BRM340 : Cement	3.4733	3.1384210297337	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.40661315273088	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.3252905221847	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.48793578327706	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.012062856864349	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	0.56925841382323	1Mtr.

6	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	1.7743970625792	Cum
i)	BRM340 : Cement	3.4733	6.1630133174563	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.79847867816064	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.63878294252851	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.95817441379277	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	7.842125257775	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.073688935611852	1Cum.

7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.7185132016128	Cum
i)	BRM340 : Cement	3.4733	2.4956119031617	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.32333094072576	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.25866475258061	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.38799712887091	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	2.7084355134794	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.053265898431763	1Cum.

8	<p>R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	-	1.8074740299264	Cum
i)	BRM340 : Cement	3.4733	6.2778995481434	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.81336331346688	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.6506906507735	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.97603597616026	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	11.24538042459	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.09076628485562	1Cum.

9	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	2.7581043452928	Cum
i)	BRM340 : Cement	0.672	1.8534461200368	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.77226921668198	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	965.33652085248	1000 Nos
10	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	9.9602092248064	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	9.9602092248064	1 Cum
ii)	BRM340 : Cement	0.672	6.6932605990699	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	2.7888585829458	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	3486.0732286822	1000 Nos
11	Flooring (AR0817ad) :.Fixing Vitrified Tile 600mm x 1200mm size of approved shade and make (Single Charge) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified Tile 600mm x 1200mm size of approved shade and make (Single Charge) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	10.953728215	Sqm
i)	BRMM332 : Vitrified Floor Tile 600mm x 1200mm size of approved shade and make (Single Charge) (New miscellaneous Materials)	1	10.953728215	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	10.953728215	1 Sqm
iii)	CON026 : cement (Other way)	0.1375	1.5061376295625	1000 kg
iv)	BRM340 : Cement	0.1375	1.5061376295625	1 Qntl.
v)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.164305923225	1 Cum

12	<p>Flooring (AR0817bbk) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in wall cladding/ glazed tiles on 12mm thick cement plaster (1:3)(For repair and maintenance) - Fixing</p> <p>Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in wall cladding/ glazed tiles on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles(For repair and maintenance).</p>	-	1.672254	Sqm
i)	<p>BRM132 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous)</p>	1	1.672254	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	0.229934925	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.02508381	1 Cum

13	Plastering (AR1004) ::12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	46.6940883136	Sqm
i)	BRM340 : Cement	0.0358	1.6716483616269	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.700411324704	1 Cum
14	Plastering (AR1014) ::16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	35.71005514	Sqm
i)	BRM340 : Cement	0.043	1.53553237102	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	0.64278099252	1 Cum

15	Concrete (AR0317) :.2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge. (new work)	-	17.9698185168	Sqm
i)	BRM340 : Cement	0.1208	2.1707540768294	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0169	0.30368993293392	1 Cum
iii)	BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	0.30368993293392	1 Cum.
16	Plastering (AR1026k) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside (inside)(For repair and maintenance). - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge(For repair and maintenance).	-	10.683845	Sqm
i)	BRM340 : Cement	0.0271	0.2895321995	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.0801288375	1 Cum

17	Painting(AR0901a) :.Priming one coat in inner surface with primer of approved quality over woodwork - Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	93.08787697	Sqm
i)	BRM138 : Wood Primer	0.075	6.98159077275	1 Litre
18	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	46.39390014	Sqm
i)	BRM142 : Distemper	0.25	11.598475035	1 Kg.
19	Painting(AR0918Ai) :.Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	46.69397683	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075	3.50204826225	1 Ltr

20	Iron Work(AR1704) :Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	2.75335	Qntl
i)	BRM341 : Steel	1	2.75335	1 Qntl.
21	miscellaneous(ARM105) :.Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.	-	6.67136443	Sqm
i)	BRMM105 : Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works)	1	6.67136443	Sqm
22	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	6.94	Qntl
i)	BRM162 : Binding Wire.	0.8	5.552	1 Kg.
ii)	BRM341 : Steel	1.05	7.287	1 Qntl.

23	Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	19.279695075	Sqm
i)	BRM141 : Enamel paint	0.125	2.409961884375	1 Litre

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	13.6561732352	1 Cum	478.15	6529.6992324109
2	BRM340	47.454818456949	1 Qntl.	559.747	26562.692266822
3	BRM028	10.004429282491	1 Cum	743.49	7438.1931272391
4	BRM044	2.331419553792	1 Cum.	1596.76	3722.7174867129
5	BRM060	2.6889527080673	1 Cum.	2003.51	5387.34364014
6	BRM052	4.033429062101	1 Cum.	1983.8	8001.5165733959
7	BRM104	0.23885667848358	1Cum.	58573.086	13990.572770493
8	BRM092	0.99740842982323	1Mtr.	229.106	228.51225572308
9	BRM084	19.087505682365	1Mtr	250.166	4775.0449465346
10	BRM094	2.7084355134794	1Mtr.	240.106	650.3116173995
11	BRM005	4451.4097495347	1000 Nos	6.2828	27967.317174377
12	BRMMR0025	9.9602092248064	1 Cum	33	328.68690441861
13	BRMM332	10.953728215	1 Sqm.	611.26	6695.5759087009
14	BRMMR0027	10.953728215	1 Sqm	8.5	93.1066898275
15	CON026	1.5061376295625	1000 kg	0	0
16	BRM132	1.672254	1 Sqm.	708.6338891	1185.015855583
17	BRM064	0.30368993293392	1 Cum.	1394.31	423.43791038909
18	BRM138	6.98159077275	1 Litre	155.44677	1085.2657350858
19	BRM142	11.598475035	1 Kg.	70.46677	817.30707264209
20	BRM255	3.50204826225	1 Ltr	195.15677	683.44842724482
21	BRM341	10.04035	1 Qntl.	6187.687	62126.54317045
22	BRMM105	6.67136443	Sqm	16.22	108.2095310546
23	BRM162	5.552	1 Kg.	90.1	500.2352
24	BRM141	2.409961884375	1 Litre	205.70677	495.74547505789
Total: 179796.4989717					