

ESTIMATION DPR							
State	Odisha	District	Balasore	Block	Basta	Gram Panchayat	Tadada

Work Code	OD/346/3301/116140/392186/00062836 (CONSTRUCTION OF MARKET COMPLEX AT TADADA CHANDI MANDIR)
Project Category	Building

Financial Year	2020-21	Execution Level	PS
Executing Agency	Panchayat Samiti, Basta	Proposal Date	08-06-2021
Date of Commencement	19-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	ASHOK KUMAR NAYAK		

Administrative Approval Details

Approval No.	OD/346/3301/116140/392186/00062836/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3301/116140/392186/00062836/TS
Fund Sanction No.	8112
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Pile Foundation(AR1501a) ∴Single under reamed pile foundation 375 mm dia and 6.0 meter long with RCC M20 using 12mm size black hard granite (Crusher broken) stone chips. - Single under-reamed pile foundation with RCC M-20 using 12mm size black granite (Crusher broken) stone chips including cost of boring and including the labour charges, convenience, royalty, taxes of all materials, labour and T&P required for the work etc. but excluding the cost of M.S./Tor steel complete and as per direction of Engineer-in charge. (375mm dia and 6.0 meter long).</p>	-	25	Nos
i)	BRM340 : Cement	3.34053	83.51325	1 Qntl.
ii)	BRM342 : Tripod	0.5	12.5	Per day
iii)	BRM178 : Bentonite powder	1.25	31.25	1Qntl
iv)	BRM028 : Screened and washed sharp sand for mortar	0.396	9.9	1 Cum
v)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.792	19.8	1 Cum.

2	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	7.773598728	Cum
i)	BRM340 : Cement	0.672	5.223858345216	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	2.17660764384	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	2720.7595548	1000 Nos
3	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	20.16740618752	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	20.16740618752	1 Cum
ii)	BRM340 : Cement	0.672	13.552496958013	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.6468737325056	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	7058.592165632	1000 Nos
4	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	37.73072016	Cum
i)	BRM029 : Sand for filling and road blinding	1	37.73072016	1 Cum
5	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	18	Qntl
i)	BRM162 : Binding Wire.	0.8	14.4	1 Kg.
ii)	BRM341 : Steel	1.05	18.9	1 Qntl.

6	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	42.0386075	Sqm
i)	BRM340 : Cement	0.0372	1.563836199	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.31528955625	1 Cum
7	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge.	-	67.4661586	Sqm
i)	BRM340 : Cement	0.0358	2.41528847788	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.011992379	1 Cum

8	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	100.613949	Sqm
i)	BRM340 : Cement	0.043	4.326399807	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.811051082	1 Cum
9	Plastering (AR1017) :.20mm thick cement Plaster in CM (1:4) over masonry work in inside. - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	55.6024455	Sqm
i)	BRM340 : Cement	0.0744	4.1368219452	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.021	1.1676513555	1 Cum

10	R.C.C. Work (AR0410d) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	49.6411944408	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	27.420850262537	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.25766143781177	1Cum.
11	R.C.C. Work (AR0410e) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	9.56715094	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	2.5757714069231	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.050656837669487	1Cum.

12	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	55.6024455	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	34.5970772	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.005022222222222	0.2792478374	1Cum.
13	R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	23.272188811059	Cum
i)	BRM340 : Cement	3.4733	80.831293397451	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	10.472484964977	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	8.3779879719812	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	12.566981957972	1 Cum.
14	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	35.75650664	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0954698727288	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.50531983664	1Mtr.

15	Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-		38.276036	Sqm
i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1		38.276036	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1		38.276036	1 Sqm
iii)	BRM340 : Cement	0.1375		5.26295495	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015		0.57414054	1 Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM340	200.82620007976	1 Qntl.	570.467	114564.7198809
2	BRM342	12.5	Per day	450	5625
3	BRM178	31.25	1Qntl	337.87	10558.4375
4	BRM028	33.076091254072	1 Cum	743.49	24591.74308649
5	BRM056	19.8	1 Cum.	2580.53	51094.494
6	BRM005	9779.351720432	1000 Nos	6.89015	67381.200256535
7	BRMMR0025	20.16740618752	1 Cum	33	665.52440418816
8	BRM029	37.73072016	1 Cum	738.55	27866.023374168
9	BRM162	14.4	1 Kg.	90	1296
10	BRM341	18.9	1 Qntl.	6379.007	120563.2323

11	BRM084	62.017927462537	1Mtr	250.166	15514.776841593
12	BRM104	0.68303598561006	1Cum.	58573.086	40007.525526233
13	BRM094	2.5757714069231	1Mtr.	240.106	618.45816943067
14	BRM060	8.3779879719812	1 Cum.	2602.58	21804.383936119
15	BRM052	12.566981957972	1 Cum.	2566.2	32249.389100547
16	BRM092	4.50531983664	1Mtr.	229.106	1032.1958064932
17	BRM131	38.276036	1 Sqm.	660.6811111	25288.253992984
18	BRMMR0027	38.276036	1 Sqm	8.5	325.346306
Total: 561046.70448168					