

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Gopabandhu nagar	Gram Panchayat	Sainkula

Work Code	OD/365/3494/120159/390967/00065526 (Improvement of Road from PWD road to Boula Chhaka at Kaliapada)
Project Category	Road

Financial Year	2020-21	Execution Level	PS
Executing Agency	Panchayat Samiti, Gopabandhunagar	Proposal Date	-
Date of Commencement	25-02-2026	Date of Completion	19-03-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	Earthen Road	Project Type	Upgradation or Improvement
Name of Executant	JADUMANI NAIK		

Administrative Approval Details

Approval No.	OD/365/3494/120159/390967/00065526/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3494/120159/390967/00065526/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	137025

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.8804691101632	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.9990959968832	Cum
i)	BRM029 : Sand for filling and road blinding	1	7.9990959968832	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.32572536752	Cum
i)	BRM340 : Cement	2.29	23.645911091621	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.9563481764096	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.9126963528192	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	7.48886480896	Cum
i)	BRM340 : Cement	3.23	24.189033332941	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.369989164032	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	6.739978328064	1 Cum.
5	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	16.8003741334	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.044856998936178	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	2.1168471408084	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	7.9990959968832	1 Cum	336.44	2691.2158571914
2	BRM340	47.834944424562	1 Qntl.	650.622	31122.467211397
3	BRM028	8.3263373404416	1 Cum	342.86	2854.7680205438
4	BRM044	9.9126963528192	1 Cum.	1726.96	17118.830093465
5	BRM056	6.739978328064	1 Cum.	2128.33	14344.898074968
6	BRM104	0.04485699893617 8	1Cum.	58573.086	2627.4128563907
7	BRM092	2.1168471408084	1Mtr.	229.106	484.98238104205
Total: 71244.574494998					