

ESTIMATION DPR							
State	Odisha	District	Jajpur	Block	Rasulpur	Gram Panchayat	Jabara

Work Code	OD/356/3402/118471/401507/00063435 (Provision of Facility Center at Jabara GP office)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Rasulpur	Proposal Date	-
Date of Commencement	24-11-2025	Date of Completion	07-04-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	SUCHISMITA BISWAL		

Administrative Approval Details

Approval No.	OD/356/3402/118471/401507/00063435/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/356/3402/118471/401507/00063435/TS
Fund Sanction No.	19201
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0122Ai) :.Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift - Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	17.7687	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.27465	Cum
i)	BRM029 : Sand for filling and road blinding	1	9.27465	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.1831	Cum
i)	BRM340 : Cement	2.29	14.159299	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.967888	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	5.935776	1 Cum.

4	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	0.9775	Cum
i)	BRM340 : Cement	0.672	0.65688	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.2737	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	342.125	1000 Nos
5	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	25.0496	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	25.0496	1 Cum
ii)	BRM340 : Cement	0.672	16.8333312	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	7.013888	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	8767.36	1000 Nos
6	Masonry Brick Work (AR0602bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure having crushing strength not less than 75.00 Kg/cm2 immersing the with dimensional tolerance \pm 8 percent immersing in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	1.6246	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1.6246	1 Cum
ii)	BRM340 : Cement	1	1.6246	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.454888	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	568.61	1000 Nos

7	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	2.7225	Cum
i)	BRM340 : Cement	3.4733	9.45605925	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.225125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.9801	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.47015	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.0109036125	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.5145525	1Mtr.

8	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	1.63125	Cum
i)	BRM340 : Cement	3.4733	5.665820625	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.7340625	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.58725	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.880875	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0217771875	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1.0276875	1Mtr.

9	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.766625	Cum
i)	BRM340 : Cement	3.4733	6.1360186125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.79498125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.635985	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.9539775	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	6.6592929375	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.1309660944375	1Cum.

10	<p>R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	-	3.834875	Cum
i)	BRM340 : Cement	3.4733	13.3196713375	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.72569375	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.380555	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.0708325	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	16.94861355	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.159258523875	1Cum.

11	R.C.C. Work (AR0404Af) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Sun sheds & Chajja)	-	4.98	Sqm
i)	BRM340 : Cement	0.21708125	1.081064625	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.028125	0.1400625	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.0225	0.11205	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.03375	0.168075	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.68432	3.4079136	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00552344	0.0275067312	1Cum.

12	<p>R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	-	7.599384	Cum
i)	BRM340 : Cement	3.4733	26.3949404472	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.4197228	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.73577824	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.10366736	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	47.2803274944	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.3816197862048	1Cum.

13	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	20.61	Qntl
i)	BRM162 : Binding Wire.	0.8	16.488	1 Kg.
ii)	BRM341 : Steel	1.05	21.6405	1 Qntl.
14	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	98.3632	Sqm
i)	BRM340 : Cement	0.0358	3.52140256	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.475448	1 Cum

15	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	150.6932	Sqm
i)	BRM340 : Cement	0.043	6.4798076	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.7124776	1 Cum
16	Painting(AR0901di) :.Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface) - Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	248.695	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	22.462774193548	1 Ltr
17	Painting(AR0918cb) :.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	295.78	Sqm

i)	BRM255 : Weather Coat (I.S.I.)	0.125	36.9725	1 Ltr
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	26.715612903226	1 Ltr
18	Flooring (AR0816a) :.Fixing Marble Tiles in floor, treads or steps and landing of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm Above 0.10 Sqm. to 0.40 Sqm on a 25mm thick bed of cement mortar 1:1 - Fixing Marble Tiles in floor, treads or steps and landing of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm Above 0.10 Sqm. to 0.40 Sqm on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the marble tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	32.4304	Sqm
i)	BRM118 : Marble Tiles of minimum 16 mm thick, dunguri Variety (Above 0.10 Sqm. to 0.40 Sqm)	1	32.4304	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	32.4304	1 Sqm
iii)	BRM340 : Cement	0.2737	8.87620048	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.4215952	1 Cum

19	Flooring (AR0817af) :.Fixing Marble Tiles of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Marble Tiles of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm in dados, skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Marble tiles including rubbing and polishing complete including cost of precast tiles.	-	4.9785	Sqm
i)	BRM117 : Marble Tiles of minimum 16 mm thick, dunguri Variety (Up to 0.10 Sqm.)	1	4.9785	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	4.9785	1 Sqm
iii)	CON026 : cement (Other way)	0.1375	0.68454375	1000 kg
iv)	BRM340 : Cement	0.1375	0.68454375	1 Qntl.
v)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.0746775	1 Cum

20	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	46.7376	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	46.7376	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	6.42642	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.701064	1 Cum

21	<p>Flooring (AR0817aq) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge(For repair and maintenance) .</p>	-	11.1216	Sqm
i)	BRM123 : Granite Tiles Up to 0.10 Sqm. (10mm thick)	1	11.1216	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	11.1216	1 Sqm
iii)	CON026 : cement (Other way)	0.1375	1.52922	1000 kg
iv)	BRM340 : Cement	0.1375	1.52922	1 Qntl.
v)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.166824	1 Cum
22	<p>Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.</p>	-	17.65245	Sqm

i)	BRM137 : Red oxide Primer	0.054	0.9532323	1 Litre
ii)	BRM141 : Enamel paint	0.125	2.20655625	1 Litre

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	9.27465	1 Cum	413.05	3830.8941825
2	BRM340	122.8452794872	1 Qntl.	568.667	69858.056550148
3	BRM028	24.3020981	1 Cum	417.99	10158.033984819
4	BRM044	5.935776	1 Cum.	1776.47	10544.72799072
5	BRM005	9678.095	1000 Nos	6.04185	58473.59827575
6	BRMMR0025	26.6742	1 Cum	33	880.2486
7	BRM060	6.43171824	1 Cum.	2250.97	14477.604806693
8	BRM052	9.64757736	1 Cum.	2218.16	21399.870196858
9	BRM104	0.7320319357173	1Cum.	58573.086	42877.369525516
10	BRM092	1.54224	1Mtr.	229.106	353.33643744
11	BRM094	6.6592929375	1Mtr.	240.106	1598.9361900514
12	BRM084	67.6368546444	1Mtr	250.166	16920.441378971
13	BRM162	16.488	1 Kg.	90.1	1485.5688
14	BRM341	21.6405	1 Qntl.	6217.337	134546.2813485
15	BRM253	49.178387096774	1 Ltr	155.84787	7664.3468790677
16	BRM255	36.9725	1 Ltr	193.24787	7144.856873575
17	BRM118	32.4304	1 Sqm.	680.5011111	22068.923233417
18	BRMMR0027	48.5305	1 Sqm	8.5	412.50925
19	BRM117	4.9785	1 Sqm.	560.2011111	2788.9612316114
20	CON026	2.21376375	1000 kg	0	0
21	BRM129	46.7376	1 Sqm.	414.8011111	19386.808410147
22	BRM123	11.1216	1 Sqm.	1185.2011111	13181.33267721
23	BRM137	0.9532323	1 Litre	140.74787	134.1654158402
24	BRM141	2.20655625	1 Litre	200.44787	442.29950034769

Total: 460629.17173918