

ESTIMATION DPR							
State	Odisha	District	Koraput	Block	Lamtaput	Gram Panchayat	Lamtaput

Work Code	OD/363/3474/119849/429578/00035359 (Improvement of Road with Paver Block at Sargiguda)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Lamtaput	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	Pavor Block	Project Type	Upgradation or Improvement
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	35917
Fund Sanction Amount (in Rs.)	221855

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0110) :.Fine dressing of earth work in ordinary or hard soil in road formation - Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.	-	208.8	Sqm

2	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	8.256	Cum
3	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	22.512	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	22.512	1 Cum
4	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	11.52	Cum
i)	<p>BRM340 : Cement</p>	2.29	26.3808	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.48	5.5296	1 Cum

iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	11.0592	1 Cum.
5	Concrete (AR0307) :Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	0.864	Cum
i)	BRM340 : Cement	3.23	2.79072	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.3888	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	0.7776	1 Cum.

6	<p>miscellaneous(ARM287) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	170.4	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	5.112	1 Cum
ii)	BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	170.4	1 Sqm

7	R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	81.12	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.2165904	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	10.22112	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	27.624	1 Cum	673.45	18603.3828
2	BRM340	29.17152	1 Qntl.	571.157	16661.51784864
3	BRM028	5.9184	1 Cum	677.37	4008.946608
4	BRM044	11.0592	1 Cum.	1596.76	17658.888192
5	BRM056	0.7776	1 Cum.	1998.13	1553.745888
6	BRMM287	170.4	1 Sqm	608.4	103671.36
7	BRM104	0.2165904	1Cum.	58573.086	12686.368125974
8	BRM092	10.22112	1Mtr.	229.106	2341.71991872
Total: 177185.92938133					