

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	Chakapad	Gram Panchayat	Brahmanpada

Work Code	OD/359/3423/118883/416032/00035745 (RENOVATION OF MARKET COMPLEX AT BRAHMANPADA)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Chakapad	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Market Complex	Project Type	Renovation or Rejuvenation
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	OD/359/3423/118883/416032/00035745/TS
Fund Sanction No.	33742
Fund Sanction Amount (in Rs.)	400000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Measurement Qty)	Unit
1	Dismantling (AR1603) :.Dismantling brick or stone masonry under 3m. - Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.	-	45.8307408	Cum

2	<p>Dismantling (AR1624) :.Dismantling and removing R.C.C. columns beams slab staircase landing lintels - Dismantling and removing R.C.C. columns beams slab staircase landing lintels including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.</p>	-	21.650600528	Cum
3	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	54.404501504	Cum
4	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	36.574226652	Cum
i)	BRM029 : Sand for filling and road blinding	1	36.574226652	1 Cum

5	<p>Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	17.68585775616	Cum
i)	BRM340 : Cement	2.29	40.500614261606	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	8.4892117229568	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	16.978423445914	1 Cum.
6	<p>R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	-	10.749984060547	Cum
i)	BRM340 : Cement	3.4733	37.337919637498	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.8374928272461	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.8699942617969	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	5.8049913926954	1 Cum.
7	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	8.06175	Qntl
i)	BRM162 : Binding Wire.	0.8	6.4494	1 Kg.
ii)	BRM341 : Steel	1.05	8.4648375	1 Qntl.
8	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	57.7898652156	Sqm

i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.15429894012565	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	7.2815230171656	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	36.574226652	1 Cum	697.55	25512.351801103
2	BRM340	77.838533899104	1 Qntl.	608.852	47392.147041537
3	BRM028	13.326704550203	1 Cum	704.43	9387.7304862995
4	BRM045	16.978423445914	1 Cum.	1414.91	24022.941117858
5	BRM060	3.8699942617969	1 Cum.	2602.58	10071.969665867
6	BRM052	5.8049913926954	1 Cum.	2566.2	14896.768911935
7	BRM162	6.4494	1 Kg.	90.1	581.09094
8	BRM341	8.4648375	1 Qntl.	7109.632	60181.8795648
9	BRM104	0.15429894012565	1Cum.	58620.646	9045.103547281
10	BRM092	7.2815230171656	1Mtr.	276.666	2014.5498470671
Total: 203106.53292375					