

ESTIMATION DPR

State	Odisha	District	Bargarh	Block	Bijepur	Gram Panchayat	Badbramahani
--------------	--------	-----------------	---------	--------------	---------	-----------------------	--------------

Work Code	OD/347/3316/116456/380401/00044746 (Provision of Facilities at Badbrahmani GP)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Bijepur	Proposal Date	-
Date of Commencement	11-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	ASHISH TIWARI		

Administrative Approval Details

Approval No.	OD/347/3316/116456/380401/00044746/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/347/3316/116456/380401/00044746/TS
Fund Sanction No.	27859
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	34.01272432	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	37.327182540224	Cum
i)	BRM029 : Sand for filling and road blinding	1	37.327182540224	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.811181734054	Cum
i)	BRM340 : Cement	2.29	24.757606170984	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	5.1893672323459	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	10.378734464692	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	3.880428084	Cum
i)	BRM340 : Cement	3.4733	13.477890864157	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.7461926378	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.39695411024	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.09543116536	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.01554111447642	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.733400907876	1Mtr.

5	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	3.2349193589216	Cum
i)	BRM340 : Cement	3.4733	11.235845409342	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.4557137115147	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.1645709692118	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.7468564538177	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.043186173441603	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	2.0379991961206	1Mtr.

6	<p>R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	-	3.1770245569664	Cum
i)	BRM340 : Cement	3.4733	11.034759393711	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.4296610506349	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.1437288405079	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.7155932607619	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	14.041177731969	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.13193865282626	1Cum.

7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	3.29041216	Cum
i)	BRM340 : Cement	3.4733	11.428588555328	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.480685472	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.1845483776	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.7768225664	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	12.40320863712	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.24392976986336	1Cum.

8	<p>R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	-	8.85406021216	Cum
i)	BRM340 : Cement	3.4733	30.752807334895	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.984327095472	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.1874616763776	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.7811925145664	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	55.086421015975	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.44462611248608	1Cum.

9	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	108.26172396	Sqm
i)	BRM340 : Cement	0.0358	3.875769717768	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.6239258594	1 Cum
10	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp. and as per direction of Engineer-in-charge.	-	173.341390296	Sqm
i)	BRM340 : Cement	0.043	7.453679782728	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	3.120145025328	1 Cum
11	Iron Work(AR1702) :.Iron work wrought and put up in window grating including drilling holes in choukathas - Iron work wrought and put up in window grating including drilling holes in choukathas including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	-	7.73	Qntl
i)	BRM341 : Steel	1	7.73	1 Qntl.

12	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	43.01873415	Sqm
i)	BRM174 : White Cement.	0.0076	0.32694237954	1Qntl
ii)	BRM340 : Cement	0.1074	4.62021204771	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.90339341715	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	43.01873415	1 Sqm.

13	<p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	4.71111113	Sqm
i)	<p>BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	4.71111113	1 Sqm.
ii)	<p>BRMMR0027 : Wax Polish</p>	1	4.71111113	1 Sqm
iii)	<p>BRM340 : Cement</p>	0.1375	0.647777780375	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.07066666695	1 Cum

14	Flooring (AR0817a) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge	-	12.432836878	Sqm
i)	BRMMR0027 : Wax Polish	1	12.432836878	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	12.432836878	1 Sqm.
iii)	BRM340 : Cement	0.1375	1.709515070725	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.18649255317	1 Cum

15	<p>Flooring (AR0817bk) :.Fixing Ceramic Tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3)(For repair and maintenance) - Fixing Ceramic Tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles, including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge(For repair and maintenance) .</p>	-	31.276352368	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	31.276352368	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	4.3004984506	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.46914528552	1 Cum

16	<p>Other Building Items. (AR1902) :.cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	227.48042774	Sqm
i)	BRMMR0038 : Cement based putty	0.8	181.984342192	kg
17	<p>Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	227.48042774	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	28.4350534675	1 Litre
18	<p>Painting(AR0918cb) :.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p>	-	108.26172396	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	13.532715495	1 Ltr
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	9.7784782931613	1 Ltr

19	Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	38.11345575	Sqm
i)	BRM137 : Red oxide Primer	0.054	2.0581266105	1 Litre
ii)	BRM141 : Enamel paint	0.125	4.76418196875	1 Litre
20	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	18.768	Qntl
i)	BRM162 : Binding Wire.	0.8	15.0144	1 Kg.
ii)	BRM341 : Steel	1.05	19.7064	1 Qntl.

21	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	11.0665594	Cum
i)	BRM340 : Cement	0.672	7.4367279168	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	3.098636632	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	3873.29579	1000 Nos
22	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	20.544510924	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	20.544510924	1 Cum
ii)	BRM340 : Cement	0.672	13.805911340928	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.75246305872	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	7190.5788234	1000 Nos

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	37.327182540224	1 Cum	466.51	17413.50392684
2	BRM340	146.53758983605	1 Qntl.	642.957	94217.369148218
3	BRM028	30.510815698006	1 Cum	474.14	14466.398155052
4	BRM044	10.378734464692	1 Cum.	1484.59	15408.165398937
5	BRM060	8.0772639739373	1 Cum.	1946.06	15718.84032912
6	BRM052	12.115895960906	1 Cum.	1877.95	22753.046819783
7	BRM104	0.87922182309372	1Cum.	58573.086	51498.735457145
8	BRM092	2.7714001039966	1Mtr.	229.106	634.94439222625
9	BRM084	69.127598747943	1Mtr	250.166	17293.374868378
10	BRM094	12.40320863712	1Mtr.	240.106	2978.0848130243
11	BRM341	27.4364	1 Qntl.	6402.267	175655.1583188
12	BRM174	0.32694237954	1Qntl	2053.857	671.49289481489
13	BRM131	47.72984528	1 Sqm.	663.9538891	31690.416399797
14	BRMMR0027	17.143948008	1 Sqm	8.5	145.723558068
15	BRM130	12.432836878	1 Sqm.	462.9538891	5755.830185216
16	BRM129	31.276352368	1 Sqm.	418.0738891	13075.826271352
17	BRMMR0038	181.984342192	kg	30	5459.53026576
18	BRM140	28.4350534675	1 Litre	254.82677	7246.0128299003
19	BRM255	13.532715495	1 Ltr	195.15677	2641.0010453332
20	BRM253	9.7784782931613	1 Ltr	157.50677	1540.1765314709
21	BRM137	2.0581266105	1 Litre	143.06677	294.44952641528
22	BRM141	4.76418196875	1 Litre	205.70677	980.0244844838
23	BRM162	15.0144	1 Kg.	90.1	1352.79744
24	BRM005	11063.8746134	1000 Nos	6.59565	72973.444593872

25	BRMMR0025	20.544510924	1 Cum	33	677.968860492
					Total: 572542.3165145