

ESTIMATION DPR							
State	Odisha	District	Nayagarh	Block	Nayagarh	Gram Panchayat	Khuntubandha

Work Code	OD/367/3527/120669/406266/00050878 (MAINTENANCE OF KHUNTABANDHA KALYAN MANDAP)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Nayagarh	Proposal Date	-
Date of Commencement	05-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Kalyan Mandap	Project Type	Repair and Maintenance
Name of Executant	Manoja Kumar Sethi		

Administrative Approval Details

Approval No.	OD/367/3527/120669/406266/00050878/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/367/3527/120669/406266/00050878/TS
Fund Sanction No.	1313
Fund Sanction Amount (in Rs.)	500000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	25.4957388	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.6422484	Cum
i)	BRM029 : Sand for filling and road blinding	1	3.6422484	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.403883944	Cum
i)	BRM340 : Cement	2.29	5.50489423176	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	1.15386429312	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	2.30772858624	1 Cum.

4	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	1.1751472	Cum
i)	BRM340 : Cement	0.672	0.7896989184	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.329041216	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	411.30152	1000 Nos

5	<p>R.C.C. Work (AR0404Ba) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9).</p>	-	6.046132344	Cum
i)	<p>BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)</p>	0.36	2.17660764384	1 Cum.
ii)	<p>BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)</p>	0.54	3.26491146576	1 Cum.
iii)	<p>BRM340 : Cement</p>	3.4733	21.000031470415	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.45	2.7207595548	1 Cum

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.02421476003772	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1.142719013016	1Mtr.
6	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	10.22049022784	Cum
i)	BRM340 : Cement	3.4733	35.498828708357	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.599220602528	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.6793764820224	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	5.5190647230336	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.13644354454166	1Cum.

vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	6.4389088435392	1Mtr.
7	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	3.0068773441728	Cum
i)	BRM340 : Cement	3.4733	10.443787079515	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.3530948048778	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.0824758439022	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.6237137658533	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	13.289195110306	1Mtr

vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.12487260922615	1Cum.
8	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	24.0905176	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	24.0905176	1 Cum
ii)	BRM340 : Cement	0.672	16.1888278272	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	6.745344928	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	8431.68116	1000 Nos

9	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	12.753	Qntl
i)	BRM162 : Binding Wire.	0.8	10.2024	1 Kg.
ii)	BRM341 : Steel	1.05	13.39065	1 Qntl.
10	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	137.9653121507	Sqm
i)	BRM340 : Cement	0.0358	4.9391581749951	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	2.0694796822605	1 Cum

11	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	141.39929503	Sqm
i)	BRM340 : Cement	0.043	6.08016968629	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.54518731054	1 Cum
12	Painting(AR0918cb) :.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	262.59869077	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	32.82483634625	1 Ltr
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	23.718591424387	1 Ltr

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	3.6422484	1 Cum	410.7	1495.87141788
2	BRM340	100.44539609693	1 Qntl.	547.857	55029.713369477
3	BRM028	21.515992392126	1 Cum	417.13	8974.9659065276
4	BRM044	2.30772858624	1 Cum.	1230.01	2838.5292383611
5	BRM005	8842.98268	1000 Nos	6.00665	53116.701914822
6	BRM060	6.9384599697646	1 Cum.	1694.68	11758.469341561
7	BRM052	10.407689954647	1 Cum.	1636.3	17030.103072789
8	BRM104	0.28553091380554	1Cum.	58573.086	16724.42676999
9	BRM092	7.5816278565552	1Mtr.	229.106	1736.9964317039

10	BRM084	13.289195110306	1Mtr	250.166	3324.5047839648
11	BRMMR0025	24.0905176	1 Cum	33	794.9870808
12	BRM162	10.2024	1 Kg.	90.1	919.23624
13	BRM341	13.39065	1 Qntl.	6386.107	85514.12369955
14	BRM255	32.82483634625	1 Ltr	195.03787	6402.0861640712
15	BRM253	23.718591424387	1 Ltr	159.27787	3777.8467214766
					Total: 269438.56215297