

ESTIMATION DPR							
State	Odisha	District	Khordha	Block	Bolagarh	Gram Panchayat	Gediapalli

Work Code	OD/362/3461/119626/407159/00022759 (Construction of Kalyan mandap at Gediapalli GP Area)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Bolagarh	Proposal Date	-
Date of Commencement	22-09-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Kalyan Mandap	Project Type	New Work
Name of Executant	SONALI MALLICK		

Administrative Approval Details

Approval No.	OD/362/3461/119626/407159/00022759/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/362/3461/119626/407159/00022759/TS
Fund Sanction No.	32
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.717	Cum
i)	BRM029 : Sand for filling and road blinding	1	12.717	1 Cum

2	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	17.982	Cum
i)	BRM340 : Cement	2.29	41.17878	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	8.63136	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	17.26272	1 Cum.
3	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	188.148	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.50235516	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	23.706648	1Mtr.

4	R.C.C. Work (AR0410d) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	53.6	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	29.607619047619	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.27820952380952	1Cum.
5	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	45.8	Qntl
i)	BRM162 : Binding Wire.	0.8	36.64	1 Kg.
ii)	BRM341 : Steel	1.05	48.09	1 Qntl.

6	R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	50.690475	Cum
i)	BRM340 : Cement	3.4733	176.0632268175	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	22.81071375	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	18.248571	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	27.3728565	1 Cum.

7	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	140.814	Cum
---	---	---	----------------	-----

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	12.717	1 Cum	1010.1	12845.4417
2	BRM340	217.2420068175	1 Qntl.	575.332	124986.27826633
3	BRM028	31.44207375	1 Cum	1016.49	31960.553546138
4	BRM044	17.26272	1 Cum.	1726.96	29812.0269312
5	BRM104	0.78056468380952	1Cum.	58573.086	45720.082353338
6	BRM092	23.706648	1Mtr.	229.106	5431.335296688
7	BRM084	29.607619047619	1Mtr	583.086	17263.78816
8	BRM162	36.64	1 Kg.	90.1	3301.264
9	BRM341	48.09	1 Qntl.	6635.732	319112.35188
10	BRM060	18.248571	1 Cum.	2129.38	38858.14211598
11	BRM052	27.3728565	1 Cum.	2114	57866.218641
Total: 687157.48289067					