

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Morada	Gram Panchayat	Haldipal

Work Code	OD/365/3502/120284/389992/00022814 (Construction Of Kalyan Mandap At Sirsapal Village)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Morada	Proposal Date	-
Date of Commencement	15-10-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Kalyan Mandap	Project Type	New Work
Name of Executant	BIKASH CHANDRA BANERJEE		

Administrative Approval Details

Approval No.	OD/365/3502/120284/389992/00022814/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3502/120284/389992/00022814/TS
Fund Sanction No.	32
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	27.367408488	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	29.93240228144	Cum
i)	BRM029 : Sand for filling and road blinding	1	29.93240228144	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.8570143672	Cum
i)	BRM340 : Cement	2.29	22.572562900888	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	4.731366896256	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	9.462733792512	1 Cum.

4	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	70.8748718633	Sqm
i)	BRM340 : Cement	0.0372	2.6365452333148	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.53156153897475	1 Cum
5	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	99.870725	Sqm
i)	BRM340 : Cement	0.0358	3.575371955	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.498060875	1 Cum

6	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	98.01080694	Sqm
i)	BRM340 : Cement	0.043	4.21446469842	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.76419452492	1 Cum
7	R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	33.68291168	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0899333741856	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.24404687168	1Mtr.

8	R.C.C. Work (AR0410d) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm	-	49.5345417968	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	27.36193737347	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.25710785980244	1Cum.
9	R.C.C. Work (AR0410e) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	17.5218216702	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	4.7174135265923	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.092775799356315	1Cum.

10	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	73.1889834	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	45.539811893333	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.36757133885333	1Cum.
11	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	20	Qntl
i)	BRM162 : Binding Wire.	0.8	16	1 Kg.
ii)	BRM341 : Steel	1.05	21	1 Qntl.

12	Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	60.8886262	Sqm
i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	60.8886262	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	60.8886262	1 Sqm
iii)	BRM340 : Cement	0.1375	8.3721861025	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.913329393	1 Cum

13	Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	13.47650918	Sqm
i)	BRMMR0027 : Wax Polish	1	13.47650918	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	13.47650918	1 Sqm.
iii)	BRM340 : Cement	0.2737	3.688520562566	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.17519461934	1 Cum
14	Painting(AR0901a) :.Priming one coat in inner surface with primer of approved quality over woodwork - Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	184.73204132	Sqm

i)	BRM138 : Wood Primer	0.075	13.854903099	1 Litre
15	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	6.271765278672	Cum
i)	BRM340 : Cement	0.672	4.2146262672676	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.7560942780282	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	2195.1178475352	1000 Nos
16	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	15.755786084	Cum

i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	15.755786084	1 Cum
ii)	BRM340 : Cement	0.672	10.587888248448	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	4.41162010352	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	5514.5251294	1000 Nos
17	Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	20.903175	Sqm
i)	BRM141 : Enamel paint	0.125	2.612896875	1 Litre
18	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	2.66	Qntl
i)	BRM341 : Steel	1	2.66	1 Qntl.

19	R.C.C. Work (AR0404A) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	24.923272892403	Cum
i)	BRM340 : Cement	3.4733	86.566003737183	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	11.215472801581	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	8.9723782412651	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	13.458567361898	1 Cum.

20	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	194.29919226	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	24.2873990325	1 Litre

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	29.93240228144	1 Cum	531.74	15916.255589133
2	BRM340	146.42816970559	1 Qntl.	644.787	94414.980259957
3	BRM028	26.99689503062	1 Cum	538.16	14528.649029679
4	BRM044	9.462733792512	1 Cum.	1930.76	18270.26789723
5	BRM104	0.80738837219769	1Cum.	58573.086	47291.228560135
6	BRM092	4.24404687168	1Mtr.	229.106	972.33660258312
7	BRM084	72.901749266804	1Mtr	250.166	18237.539007079
8	BRM094	4.7174135265923	1Mtr.	240.106	1132.679292216
9	BRM162	16	1 Kg.	90	1440
10	BRM341	23.66	1 Qntl.	6855.747	162206.97402
11	BRM131	60.8886262	1 Sqm.	667.2266671	40626.515123724
12	BRMMR0027	74.36513538	1 Sqm	8.5	632.10365073
13	BRM130	13.47650918	1 Sqm.	466.2266671	6283.107959134
14	BRM138	13.854903099	1 Litre	155.56567	2155.347283381
15	BRM005	7709.6429769352	1000 Nos	6.4531	49751.097094461
16	BRMMR0025	15.755786084	1 Cum	33	519.940940772
17	BRM141	2.612896875	1 Litre	205.82567	537.80124993778
18	BRM060	8.9723782412651	1 Cum.	2315.51	20775.631541432
19	BRM052	13.458567361898	1 Cum.	2317.8	31194.267431406
20	BRM140	24.2873990325	1 Litre	249.82567	6067.6157358517
					Total: 532954.33826884