

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Kendujhar Sadar	Gram Panchayat	Sankiri

Work Code	OD/361/3452/119471/386007/00037695 (PRESERVATION AND DEVELOPEMENT OF JADIPADA MEDICAL SIDE POND AT VILLAGE JADIPADA GP SANKIRI)
Project Category	Water Body

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kendujhar Sadar	Proposal Date	-
Date of Commencement	11-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Preservation and Development of Water Bodies
Project Sub-Category	Tank	Project Type	Renovation or Rejuvenation
Name of Executant	Ranjan Kumar Swain		

Administrative Approval Details

Approval No.	OD/361/3452/119471/386007/00037695/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3452/119471/386007/00037695/TS
Fund Sanction No.	27848
Fund Sanction Amount (in Rs.)	663694

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	48.192503504	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.88160683424	Cum
i)	BRM029 : Sand for filling and road blinding	1	16.88160683424	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	45.13372418384	Cum
i)	BRM340 : Cement	2.29	103.35622838099	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	21.664187608243	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	43.328375216486	1 Cum.

4	Masonry Stone Work (AR0703) :.Random rubble H.G. stone of masonry. - Random rubble H.G. stone of size not less than 0.0025 cum stacked masonry in cement mortar (1:6) in foundation and plinth including watering, curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	37.69938195744	Cum
i)	BRM340 : Cement	0.8151	30.728766233509	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.34	12.81778986553	1 Cum
iii)	BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	37.69938195744	1 Cum.
5	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	3.8995631616	Cum
i)	BRM340 : Cement	3.23	12.595589011968	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.75480342272	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	3.50960684544	1 Cum.

6	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	79.3112911	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.211761147237	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0486971327354	1Mtr.
7	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	67.88793822	Sqm
i)	BRM174 : White Cement.	0.0076	0.515948330472	1Qntl
ii)	BRM340 : Cement	0.1074	7.291164564828	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	1.42564670262	1 Cum

iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	67.88793822	1 Sqm.
8	Other Building Items. (AR1911) :.Stainless steel of 304 grade in hand railing using 50mm dia of 2mm - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge	-	18.287999414784	Rmt

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	16.88160683424	1 Cum	50.25	848.30074342056
2	BRM028	37.662427599113	1 Cum	50.25	1892.5369868554
3	BRM044	43.328375216486	1 Cum.	424.5	18392.895279398
4	BRM034	37.69938195744	1 Cum.	424.5	16003.387640933
5	BRM056	3.50960684544	1 Cum.	424.5	1489.8281058893
Total: 38626.948756497					