

ESTIMATION DPR							
State	Odisha	District	Kalahandi	Block	Jayapatna	Gram Panchayat	Pratappur

Work Code	OD/358/3412/118684/424198/00064429 (CONSTRUCTION OF RURAL PARK AT CHATAPADAR KENDUGOCHHEN PLAY GROUND AMBAGICHA)
Project Category	Other Infrastructure

Financial Year	2020-21	Execution Level	PS
Executing Agency	Panchayat Samiti, Jayapatna	Proposal Date	-
Date of Commencement	19-01-2026	Date of Completion	19-02-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Innovative Practices
Project Sub-Category	Rural Park	Project Type	New Work
Name of Executant	SUSHANTA KUMAR DAS		

Administrative Approval Details

Approval No.	OD/358/3412/118684/424198/00064429/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/358/3412/118684/424198/00064429/TS
Fund Sanction No.	2117
Fund Sanction Amount (in Rs.)	1000000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	96.234	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.928	Cum
i)	BRM029 : Sand for filling and road blinding	1	20.928	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	25.878	Cum
i)	BRM340 : Cement	2.29	59.26062	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	12.42144	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	24.84288	1 Cum.

4	<p>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	29.7625	Cum
i)	BRM340 : Cement	0.672	20.0004	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	8.3335	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	10416.875	1000 Nos
5	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	38.73384	Cum
i)	BRM340 : Cement	0.672	26.02914048	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	10.8454752	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance \pm 2 %	350	13556.844	1000 Nos
6	R.C.C. Work (AR0404Aa) :Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	6.412	Cum
i)	BRM340 : Cement	3.4733	22.2707996	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.8854	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.30832	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.46248	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.02568006	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	0.005905452	1Mtr.
7	R.C.C. Work (AR0404Ab) :Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	5.725	Cum
i)	BRM340 : Cement	3.4733	19.8846425	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.57625	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.061	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.0915	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.07642875	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	0.01757575	1Mtr.
8	R.C.C. Work (AR0404Ac) :Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	4.85316	Cum
i)	BRM340 : Cement	3.4733	16.856480628	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.183922	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.7471376	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.6207064	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	0.22003742124	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.20154688164	1Cum.
9	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	14.1017	Qntl
i)	BRM341 : Steel	1.05	14.806785	1 Qntl.
10	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	360	Sqm
i)	BRM340 : Cement	0.0358	12.888	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	5.4	1 Cum
11	Painting(AR0901di) :.Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface) - Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	360	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	32.516129032258	1 Ltr
12	Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	360	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	45	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	30.24	1 Ltr

13	Flooring (AR0816j) :.Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	75	Sqm
i)	BRM340 : Cement	0.2737	20.5275	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.975	1 Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	20.928	1 Cum	40.25	842.352
2	BRM028	45.6209872	1 Cum	40.25	1836.2447348
3	BRM044	24.84288	1 Cum.	149.5	3714.01056
4	BRM060	6.1164576	1 Cum.	149.5	914.4104112
5	BRM052	9.1746864	1 Cum.	149.5	1371.6156168
Total: 8678.6333228					