

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Biramaharajpur	Gram Panchayat	Hilung

Work Code	OD/372/3568/121443/419323/00040597 (CC Road at Grampati Pitha Baghmari)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Biramaharajpur	Proposal Date	13-10-2023
Date of Commencement	10-02-2026	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	debabehera		

Administrative Approval Details

Approval No.	OD/372/3568/121443/419323/00040597/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/372/3568/121443/419323/00040597/TS
Fund Sanction No.	6140
Fund Sanction Amount (in Rs.)	200000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102a7) ∴Earthwork in hard soil or gravelly soil within 100m to 125m lead and one extra lift - Earthwork in hard soil or gravelly soil within 100m to 125m lead and one extra lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	2.76	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.87	Cum
i)	BRM029 : Sand for filling and road blinding	1	15.87	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.8125	Cum
i)	BRM340 : Cement	2.29	36.210625	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	7.59	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	15.18	1 Cum.

4	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	34.5	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.092115	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.021183	1Mtr.
5	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	12.5925	Cum
i)	BRM340 : Cement	3.23	40.673775	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.666625	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	11.33325	1 Cum.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	15.87	1 Cum	170.25	2701.8675
2	BRM028	13.256625	1 Cum	170.25	2256.94040625
3	BRM044	15.18	1 Cum.	279.5	4242.81
4	BRM056	11.33325	1 Cum.	279.5	3167.643375
Total: 12369.26128125					