

ESTIMATION DPR							
State	Odisha	District	Bargarh	Block	Attabira	Gram Panchayat	Godbhaga

Work Code	OD/347/3311/116349/380860/00030943 (Improvement of Gaon Kata,Godbhaga)
Project Category	Water Body

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Attabira	Proposal Date	30-01-2025
Date of Commencement	09-12-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	Tank	Project Type	Upgradation or Improvement
Name of Executant	Puspalata Behera		

Administrative Approval Details

Approval No.	OD/347/3311/116349/380860/00030943/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/347/3311/116349/380860/00030943/TS
Fund Sanction No.	14036
Fund Sanction Amount (in Rs.)	300000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	17.94816	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.947776	Cum
i)	BRM029 : Sand for filling and road blinding	1	7.947776	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.878464	Cum
i)	BRM340 : Cement	2.29	61.55168256	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	12.90166272	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	25.80332544	1 Cum.

4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	17.0163	Cum
i)	BRM340 : Cement	3.23	54.962649	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.657335	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	15.31467	1 Cum.
5	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	32.6952	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.087296184	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0200748528	1Mtr.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	7.947776	1 Cum	165.25	1313.369984
2	BRM028	20.55899772	1 Cum	165.25	3397.37437323
3	BRM044	25.80332544	1 Cum.	249.5	6437.92969728
4	BRM056	15.31467	1 Cum.	249.5	3821.010165
					Total: 14969.68421951