

ESTIMATION DPR							
State	Odisha	District	Bargarh	Block	Padampur	Gram Panchayat	Mahulpali

Work Code	OD/347/3319/116528/379971/00038090 (Const. of CC road at Gariba Bag house to Basti road.)						
Project Category	Road						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Padampur	Proposal Date	-
Date of Commencement	22-07-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	DASARATH MAJHI		

Administrative Approval Details

Approval No.	OD/347/3319/116528/379971/00038090/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/347/3319/116528/379971/00038090/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	200000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.5	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.08	Cum
i)	BRM029 : Sand for filling and road blinding	1	4.08	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.58	Cum
i)	BRM340 : Cement	2.29	12.7782	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.6784	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	5.3568	1 Cum.

4	Concrete (AR0307) ∴Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	22.995	Cum
i)	BRM340 : Cement	3.23	74.27385	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	10.34775	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	20.6955	1 Cum.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	4.08	1 Cum	165.25	674.22
2	BRM028	13.02615	1 Cum	165.25	2152.5712875
3	BRM044	5.3568	1 Cum.	249.5	1336.5216
4	BRM056	20.6955	1 Cum.	249.5	5163.52725
					Total: 9326.8401375