

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	Daringibadi	Gram Panchayat	Hatimunda

Work Code	OD/359/3424/118900/417264/00049397 (CONST. OF CC ROAD INFRONT OF CNI CHURCH, KASABASA)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Daringibadi	Proposal Date	-
Date of Commencement	09-12-2025	Date of Completion	17-12-2025
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	KAMAL PATRO		

Administrative Approval Details

Approval No.	OD/359/3424/118900/417264/00049397/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3424/118900/417264/00049397/TS
Fund Sanction No.	15384
Fund Sanction Amount (in Rs.)	202038

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	7.92	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	13.2	Cum
i)	BRM029 : Sand for filling and road blinding	1	13.2	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	18.48	Cum
i)	BRM340 : Cement	2.29	42.3192	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	8.8704	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	17.7408	1 Cum.

4	Concrete (AR0307) ∴Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	9.9	Cum
i)	BRM340 : Cement	3.23	31.977	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.455	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	8.91	1 Cum.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	13.2	1 Cum	40.25	531.3
2	BRM028	13.3254	1 Cum	40.25	536.34735
3	BRM044	17.7408	1 Cum.	149.5	2652.2496
4	BRM056	8.91	1 Cum.	149.5	1332.045
					Total: 5051.94195