

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Digapahandi	Gram Panchayat	Bhamarapur

Work Code	OD/354/3372/117727/413050/00017425 (Construction of all weather road from Panchayat road to Braja Bihara Nagar.)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Digapahandi	Proposal Date	07-01-2023
Date of Commencement	17-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	SANJAY SUBUDHI		

Administrative Approval Details

Approval No.	OD/354/3372/117727/413050/00017425/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3372/117727/413050/00017425/TS
Fund Sanction No.	13737
Fund Sanction Amount (in Rs.)	400000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0122Ai) :.Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift - Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	11.0032	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	33.514	Cum
i)	BRM029 : Sand for filling and road blinding	1	33.514	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	13.6344	Cum
i)	BRM340 : Cement	2.29	31.222776	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	6.544512	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	13.089024	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	7.6544	Cum
i)	BRM340 : Cement	3.23	24.723712	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	3.44448	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	6.88896	1 Cum.

5	miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	338	Sqm
i)	BRM029 : Sand for filling and road blinding	0.03	10.14	1 Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	43.654	1 Cum	554.25	24195.2295
2	BRM028	9.988992	1 Cum	554.25	5536.398816
3	BRM044	13.089024	1 Cum.	250.5	3278.800512
4	BRM056	6.88896	1 Cum.	250.5	1725.68448
Total: 34736.113308					