

ESTIMATION DPR							
State	Odisha	District	Puri	Block	Delanga	Gram Panchayat	Arisal

Work Code	OD/369/3538/120909/408575/00052741 (Cons of cc road from Khandimangalpur Prakash Pradhan House to Ajay Parida House)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Delanga	Proposal Date	-
Date of Commencement	16-03-2026	Date of Completion	10-04-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	SWAGATIKA DAS		

Administrative Approval Details

Approval No.	OD/369/3538/120909/408575/00052741/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/369/3538/120909/408575/00052741/TS
Fund Sanction No.	3004
Fund Sanction Amount (in Rs.)	201457

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.562	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.1695	Cum
i)	BRM029 : Sand for filling and road blinding	1	12.1695	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.8055	Cum
i)	BRM340 : Cement	2.29	38.484595	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	8.06664	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	16.13328	1 Cum.

4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	11.330445	Cum
i)	BRM340 : Cement	3.23	36.59733735	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.09870025	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	10.1974005	1 Cum.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	12.1695	1 Cum	110.25	1341.687375
2	BRM028	13.16534025	1 Cum	110.25	1451.4787625625
3	BRM044	16.13328	1 Cum.	409.5	6606.57816
4	BRM056	10.1974005	1 Cum.	409.5	4175.83550475

Total: 13575.579802312