

Estimate Abstract

OD/360/3435/119054/396553/00014475 : CONST OF CC ROAD FROM RD ROAD TO 8A
CANAL NEW CLUB VILL-BAZAR
Block : Derabish, Panchayat : Benipur
Created By:ABANI KUMAR MOHANTY

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0101aa (Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift) : Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum	3.6224999427795	Cubic Meter	175.30368	635.03757076904

2	<p>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	16.42200088501	Cubic Meter	749.275772	12304.6073909
3	<p>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	22.459499359131	Cubic Meter	6100.70648248	137018.81333351

4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	48.299999237061	Square Meter	215.22489289764	10395.362162752
---	--	-----------------	-----------------	-----------------	-----------------

5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	17.629499435425	Cubic Meter	7638.42757176	134661.65456388
---	--	-----------------	-------------	---------------	-----------------

Total Amount:	295015.4750218
----------------------	----------------

Provision for Contingency (+) @	2950.1547930852
Display Citizen Board (+) @	2034
Any Other Lumpsum (+) @	0

Total Amount:	299999.62981489
----------------------	-----------------

Grand Net Total Amount	299999.63410161
-------------------------------	-----------------

ABANI KUMAR MOHANTY
JE
Derabish Block

MANOJ KUMAR ROUT
AEE
Derabish Block

Namita Barik
BDO
Derabish Block