

Estimate Abstract

OD/365/3490/120105/389159/00014351 : CONSTRUCTION OF CC DRAIN FROM KARMA SINGH HOUSE TO SANDAHARAT KAINFULIA
Block : Baripada, Panchayat : Laxmiposi
Created By: BHIM CHARAN TUDU

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102a (Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	33	Cubic Meter	196.3036	6478.0188
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	8.25	Cubic Meter	1228.056172	10131.463419

3	<p>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	20.5	Cubic Meter	5983.72042872	122666.26878876
4	<p>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	120	Square Meter	215.38264180804	25845.917016965

5	<p>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	1.125	Cubic Meter	7324.66277764	8240.245624845
6	<p>Plastering : AR1006 (12mm thick cement plaster (1:4) over brickwork in inside) : 12mm thick cement plaster (1:4) over brickwork in inside with cement punning for skirting/wall punning including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc. comp. and as per direction of Engineer-in-charge.</p>	135	Square Meter	189.2253179192	25545.417919092

Total Amount:	198907.33156866
----------------------	-----------------

Provision for Contingency (+) @	1989.0733156866
Display Citizen Board (+) @	1141.5
Any Other Lumpsum (+) @	

Total Amount:	202037.90488435
----------------------	-----------------

Grand Net Total Amount	202037.90488435
-------------------------------	-----------------

BHIM CHARAN TUDU
JE
Baripada Block

SUSMITA BEHERA
AEE
Baripada Block

AISHWARYA BHUYAN
BDO
Baripada Block