

**Estimate Abstract**

**OD/345/3285/115778/420185/00014387 : Const of Drain at Kermeli**

**Block : Balangir, Panchayat : Barapudgia**

**Created By:Tani Swain**

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0101a (Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift) :</b> Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum	60.6528	Cubic Meter	146.0864	8860.54920192
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	7.488	Cubic Meter	593.099472	4441.128846336

3	<p><b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	37.128	Cubic Meter	5546.04597832	205913.59508306
4	<p><b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	2.5116	Cubic Meter	7166.50427184	17999.392129153

5	<b>Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) :</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	157.56	Square Meter	170.2568318464	26825.666425719
6	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	118.56	Square Meter	215.22489289764	25517.063301944

<b>Total Amount:</b>	289557.39498814
----------------------	-----------------

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	7442

<b>Total Amount:</b>	299999.39498814
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.39498814
-------------------------------	-----------------

**Tani Swain**  
**JE**  
**Balangir Block**

**Neincy Rani Purty**  
**AEE**  
**Balangir Block**

**HRUSHIKESH GOND**  
**BDO**  
**Balangir Block**