

Estimate Abstract

OD/361/3452/119451/386081/00016042 : CONSTRUCTION OF C.C ROAD FROM PURNA  
CHANDRA BARIK HOUSE TO AWC AT SANKARPUR

Block : Kendujhar Sadar, Panchayat : Bodapalasa

Created By: Manoj Kumar Sahoo

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in- charge	3.008376832	Cubic Meter	235.56432	708.66624273383

2	<p><b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	11.34593011712	Cubic Meter	862.304872	9783.6508173641
3	<p><b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	16.3267872768	Cubic Meter	5843.84483384	95411.211480732

4	<p><b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	10.8736512	Cubic Meter	7327.22559608	79673.695395486
5	<p><b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	39.48005888	Square Meter	215.22489289764	8497.0914440405

<b>Total Amount:</b>	194074.31538036
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	925.68

<b>Total Amount:</b>	199999.99538036
----------------------	-----------------

<b>Grand Net Total Amount</b>	199999.99538036
-------------------------------	-----------------

**Manoj Kumar Sahoo**  
**JE**  
**Kendujhar Sadar Block**

**Sabyasachi1997**  
**AEE**  
**Kendujhar Sadar Block**

**Binod Chandra Panda**  
**BDO**  
**Kendujhar Sadar Block**