

### Estimate Abstract

**OD/370/3557/121263/426287/00016594 : Construction of CC road at Station Pada  
Block : Rayagada, Panchayat : Karlakana  
Created By: BHRAMAR BARA KISHAN**

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	21.6	Cubic Meter	235.56432	5088.189312
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	10.8	Cubic Meter	627.378872	6775.6918176

3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	16.2	Cubic Meter	5260.32546232	85217.272489584
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	6.48	Cubic Meter	6827.00852784	44239.015260403

<b>Total Amount:</b>	141320.16887959
----------------------	-----------------

Provision for Contingency (+) @	1413.2016887959
Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	

<b>Total Amount:</b>	143733.37056838
----------------------	-----------------

<b>Grand Net Total Amount</b>	143733.37056839
-------------------------------	-----------------

**BHRAMAR BARA  
KISHAN  
JE  
Rayagada Block**

**RAKESH KUMAR  
SAHOO  
AEE  
Rayagada Block**

**SHRI SUJIT KUMAR  
MISHRA  
BDO  
Rayagada Block**