

Estimate Abstract

OD/364/3484/120000/430181/00015648 : Improvement Of Road At Rural Haat At Gotijodi
Block : Malkangiri, Panchayat : Pandripani
Created By:Er. TAPAN KUMAR SAMAL

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<p>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	8.464	Cubic Meter	235.56432	1993.81640448
2	<p>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	22.16	Cubic Meter	580.009872	12853.01876352

3	<p>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	34.304	Cubic Meter	5639.45833312	193455.97865935
4	<p>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	24	Cubic Meter	7314.21531744	175541.16761856

5	Road Work : AR1307 (Supplying & spreading moorum and consolidation with HRR) : Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.	7.2	Cubic Meter	977.97405489753	7041.4131952622
---	---	-----	-------------	-----------------	-----------------

Total Amount:	390885.39464117
----------------------	-----------------

Provision for Contingency (+) @	3908.8539464117
Display Citizen Board (+) @	4000
Any Other Lumpsum (+) @	1205

Total Amount:	399999.24858758
----------------------	-----------------

Grand Net Total Amount	399999.24858758
-------------------------------	-----------------

Er. TAPAN KUMAR SAMAL
JE
Malkangiri Block

Er. ABHIJIT SETHI
AEE
Malkangiri Block

Tapan kumar senapati
BDO
Malkangiri Block