

**Estimate Abstract**

**OD/347/3312/116375/380630/00016191 : Improvement Of Road From Kalangapali To  
Chakarkend**

**Block : Bargarh, Panchayat : Chakarkend**

**Created By:AKULA SAHOO**

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<p><b>Road Work : AR1308 (moorum and sand admixture laying in sub-base in layers not exceeding 100mm watering and compacting to the required density in O.M.C with PRR)</b> : Supplying &amp; spreading moorum and sand admixture in a ratio (70:30) laying in sub-base in layers not exceeding 100mm watering and compacting to the required density in O.M.C with PRR including cost, conveyance, royalty, taxes cost of all labour &amp; material, hire charges of T &amp; P materials required for work as per specification and complete as per direction of Engineer-in-Charge.</p>	675	Cubic Meter	1177.3115835834	794685.3189188

<b>Total Amount:</b>	794685.3189188
----------------------	----------------

Provision for Contingency (+) @	2314
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	

<b>Total Amount:</b>	799999.3189188
----------------------	----------------

<b>Grand Net Total Amount</b>	799999.3189188
-------------------------------	----------------

**AKULA SAHOO**  
**JE**  
**Bargarh Block**

**SUNIL KUMAR PRUSTY**  
**AEE**  
**Bargarh Block**

**BERCIUS DUNGDUNG**  
**BDO**  
**Bargarh Block**