

Estimate Abstract

OD/361/3452/119468/386138/00015527 : Provision of Facility center at Raghunathpur GP
head QTR

Block : Kendujhar Sadar, Panchayat : Raghunathpur

Created By:Samir Kabi

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	23.19	Cubic Meter	235.56432	5462.7365808

2	<p>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	34.358395392	Cubic Meter	1051.841472	36139.585184679
3	<p>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	8.4154	Cubic Meter	5937.07439884	49962.855895998

4	<p>Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	15.60075	Cubic Meter	5224.294842712	81502.917767439
---	---	----------	-------------	----------------	-----------------

5	<p>R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	3.6	Cubic Meter	6519.8447268133	23471.441016528
---	---	-----	-------------	-----------------	-----------------

6	<p>R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)</p>	2.55125	Cubic Meter	7273.131851955	18555.5776373
---	---	---------	-------------	----------------	---------------

7	<p>R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	4.91625	Cubic Meter	14471.290364133	71144.481252669
---	---	---------	-------------	-----------------	-----------------

8	<p>R.C.C. Work : AR0404Ad (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)</p>	1.53075	Cubic Meter	13140.320205344	20114.54515433
---	---	---------	-------------	-----------------	----------------

9	<p>R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	9.30155	Cubic Meter	12761.528081203	118701.99152371
---	--	---------	-------------	-----------------	-----------------

10	<p>Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	24.32725	Cubic Meter	5257.624842712	127903.55395487
----	---	----------	-------------	----------------	-----------------

11	<p>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	21.84	Quintal	9246.0884098	201934.57087003
12	<p>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	113.9698	Square Meter	248.830006228	28359.106043804

13	<p>Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	147.7638	Square Meter	174.5287612168	25789.032966687
14	<p>Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	64.0476	Square Meter	190.8540410912	12223.743282193

15	<p>Flooring : AR0816k (Fixing tiles in floors(30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755)(For repair and maintenance)) : Fixing Marble Tiles in floor (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755), treads, or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge(For repair and maintenance) .</p>	5.9168	Square Meter	1284.9655316262	7602.8840575259
----	---	--------	--------------	-----------------	-----------------

16	<p>Flooring : AR0817bk (Fixing tiles(20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3)(For repair and maintenance)) :</p> <p>Fixing Marble Tiles in floor (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge(For repair and maintenance) .</p>	17.94	Square Meter	960.837364331	17237.422316098
----	--	-------	--------------	---------------	-----------------

17	<p>Flooring : AR0817ba (Fixing Vitrified floor tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Plain (Ivory) in wall cladding/ glazed tiles on 12mm thick cement plaster (1:3)) : Fixing Vitrified floor tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Plain (Ivory) in wall cladding/ glazed tiles on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.</p>	6.1845	Square Meter	1253.877148331	7754.6032238531
----	--	--------	--------------	----------------	-----------------

18	<p>Other Building Items. : AR1901Bd (Vitrified Tile 600mmx600mm Vitrified floor tile 1200mmx1800mm) : Supplying, fitting & fixing Vitrified floor tile of size 1200mmx1800mm of approved shade & make(Single charge) of premium grade having thickness 8mm to 10mm conforming to IS 4457 of size 300mmx300mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge.</p>	37.6652	Square Meter	1336.9671740328	50357.13600338
19	<p>Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	4.42617	Quintal	16401.911264976	72597.647583699

Total Amount:	976815.8323156
----------------------	----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	9768.158323156
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	10416

Total Amount:	999999.99063875
----------------------	-----------------

Grand Net Total Amount	999999.99063876
-------------------------------	-----------------

Samir Kabi
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block