

Estimate Abstract

OD/372/3570/121486/418949/00017040 : Maintenace of road from Raipali to Rengali High School, Boxel Bridges
Block : Sonapur, Gram Panchayat : Rengali
Created By:Smt Supriya Guru

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<p>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	51.316647	Cubic Meter	240.77592	12355.81289274
2	<p>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	11.261805	Cubic Meter	646.807232	7284.2169193738

3	<p>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	94.138784	Cubic Meter	5844.94759224	550236.2588772
4	<p>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	218.0336	Square Meter	216.39264180804	47180.866706917

5	<p>R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	2.49522	Cubic Meter	6430.4671971369	16045.43035964
---	---	---------	-------------	-----------------	----------------

6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	9	Quintal	8940.5702778	80465.1325002
---	---	---	---------	--------------	---------------

Total Amount:	713567.71825607
----------------------	-----------------

Provision for Contingency (+) @	0
Display Citizen Board (+) @	1100
Any Other Lumpsum (+) @	

Total Amount:	714667.71825607
----------------------	-----------------

Grand Net Total Amount	714667.71825607
-------------------------------	-----------------

Smt Supriya Guru
JE
Sonepur Block

Baijayantee Karna
AEE
Sonepur Block

Sri Prateek Kar
BDO
Sonepur Block