

Estimate Abstract

**OD/372/3570/121485/419623/00017042 : Preservation and Development of Nua Bandha,
Narayanapur**

Block : Sonapur, Gram Panchayat : Narayanpur

Created By:Smt Supriya Guru

| Sl No | Description of work | Quantity | Unit | Rate in (Rs.) | Amount (Rs.) |
|-------|--|------------|-------------|---------------|----------------|
| 1 | <p>Special items for irrigation works : AR0216 (Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum) :</p> <p>Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.</p> | 9855.71648 | Cubic Meter | 67.165 | 661959.1973792 |

| | |
|----------------------|----------------|
| Total Amount: | 661959.1973792 |
|----------------------|----------------|

| | |
|-----------------------------|------|
| Display Citizen Board (+) @ | 1700 |
| Any Other Lumpsum (+) @ | 0 |

| | |
|----------------------|----------------|
| Total Amount: | 663659.1973792 |
|----------------------|----------------|

| | |
|-------------------------------|----------------|
| Grand Net Total Amount | 663659.1973792 |
|-------------------------------|----------------|

Smt Supriya Guru
JE
Sonepur Block

Baijayantee Karna
AEE
Sonepur Block

Sri Prateek Kar
BDO
Sonepur Block