

Estimate Abstract

OD/367/3527/275496/406388/00013784 : MAINT OF MANGARAJPUR NANI BANK
POKHARI

Block : Nayagarh, Gram Panchayat : Chandibasta
Created By: Monalisa Satapathy

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Special items for irrigation works : AR0216 (Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum) : Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.	1467	Cubic Meter	67.165	98531.055

Total Amount:	98531.055
----------------------	-----------

Display Citizen Board (+) @	1468
Any Other Lumpsum (+) @	

Total Amount:	99999.055
----------------------	-----------

Grand Net Total Amount	99999.055
-------------------------------	-----------

Monalisa Satapathy
JE
Nayagarh Block

Chandra Sekhar Samantaray
AEE
Nayagarh Block

Aishwarya Bhuyan
BDO
Nayagarh Block