

Estimate Abstract

OD/361/3452/119467/385986/00014335 : CONSTRUCTION OF VANA SURAKHYA
SAMITI BUILDING AT KASIRA

Block : Kendujhar Sadar, Gram Panchayat : Parjanpur

Created By:Ranjan Kumar Swain

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	29.32896419424	Cubic Meter	240.77592	7061.7083365152

2	<p>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	9.478976450576	Cubic Meter	1118.133832	10598.76426212
3	<p>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	6.920634273456	Cubic Meter	6109.40066146	42280.927607975

4	<p>Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	9.3433211956256	Cubic Meter	5251.285134928	49064.443705446
---	--	-----------------	-------------	----------------	-----------------

5	<p>R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	3.894126336	Cubic Meter	6769.7426534507	26362.233154745
---	--	-------------	----------------	-----------------	-----------------

6	<p>R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)</p>	2.070715129648	Cubic Meter	7506.41481577	15543.646728429
---	--	----------------	----------------	---------------	-----------------

7	<p>R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	3.8141306114464	Cubic Meter	14704.573327948	56085.163258385
---	--	-----------------	----------------	-----------------	-----------------

8	<p>R.C.C. Work : AR0404Ad (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)</p>	1.20234407056	Cubic Meter	13373.603169159	16079.672472461
---	--	---------------	----------------	-----------------	-----------------

9	<p>R.C.C. Work : AR0404Af (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Sun sheds & Chajja)</p>	6.78098997	Square Meter	1123.9313366712	7621.3671209361
---	---	------------	-----------------	-----------------	-----------------

10	<p>R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	5.959564629968	Cubic Meter	12994.811045018	77443.416277007
----	---	----------------	----------------	-----------------	-----------------

11	<p>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	15.53	Quintal	9261.2196238	143826.74075761
----	---	-------	---------	--------------	-----------------

12	<p>Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	19.99845824784	Cubic Meter	5240.570447312	104803.32928543
----	---	----------------	-------------	----------------	-----------------

13	<p>Plastering : AR1017 (20mm thick cement Plaster in CM (1:4) over brick work in inside.) : 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in- charge.</p>	43.57429409	Square Meter	276.1059687024	12031.122680243
----	---	-------------	-----------------	----------------	-----------------

14	<p>Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	120.4995202798	Square Meter	175.2894619068	21122.296069874
----	---	----------------	--------------	----------------	-----------------

15	<p>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	115.40968078	Square Meter	249.742606878	28822.714536955
----	--	--------------	--------------	---------------	-----------------

16	<p>Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	55.2519596422	Square Meter	191.1185055512	10559.671955592
17	<p>Flooring : AR0802ii (2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	2.0903175	Square Meter	372.1707516068	777.95503507185

18	<p>Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	29.0131981268	Square Meter	1146.2900180998	33257.539405903
----	---	---------------	--------------	-----------------	-----------------

19	<p>Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	3.26646948	Square Meter	1651.914003392	5395.9266756646
----	--	------------	-----------------	----------------	-----------------

20	<p>Flooring : AR0816 (Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Enginer-in-charge.</p>	3.5210237	Square Meter	1288.1342925972	4535.5513730175
----	---	-----------	--------------	-----------------	-----------------

21	<p>Flooring : AR0817b (Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)) : Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	10.5259099	Square Meter	964.954019392	10157.019065763
----	---	------------	--------------	---------------	-----------------

22	<p>Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in- charge.</p>	3.7605	Quintal	16416.321944976	61733.578674082
23	<p>Painting : AR0918cb (Finishing wall two coats with weather coat with one coat waterbound Primer) : Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in- charge.(Outside)</p>	122.45916042	Square Meter	158.50729281962	19410.669999138

24	<p>Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	147.35530636	Square Meter	70.773704009333	10428.880836527
25	<p>Painting : AR0922 (Finishing wall two coats with distemper of approved shades on new work (Inside)) : Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	158.19151228	Square Meter	80.95122225	12805.796268642

26	Painting : AR0903ak (Painting two coats of enamel paint with a coat of wood primer new wood work in inner surface paint (Inside)(For repair and maintenance) .) : Painting two coats of enamel paint with a coat of wood primer in new wood work inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in- charge.(Inside)(For repair and maintenance)	29.763798625	Square Meter	241.37977977742	7184.379157442
----	---	--------------	-----------------	-----------------	----------------

Total Amount:	794994.51470098
----------------------	-----------------

Provision for PH Work (+) @	24500
Provision for EI Work (+) @	19005.48
Provision for Contingency (+) @	8500
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	

Total Amount:	849999.99470098
----------------------	-----------------

Grand Net Total Amount	849999.99470098
-------------------------------	-----------------

Ranjan Kumar Swain
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block