

**Estimate Abstract**

**OD/355/3389/118117/397974/00015507 : Construction of CC Road at Kolar from Ujja Nana House to 19 no Canal Bandha, Vill-KoLar, GP-Alipingal  
Block : Jagatsinghpur, Gram Panchayat : Alipingal  
Created By:Dipti Ranjan Mohanty**

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0101aa (Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift) :</b> Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum	1.42875	Cubic Meter	179.18208	256.0063968
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	2.8575	Cubic Meter	544.049832	1554.62239494

3	<p><b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	7.14375	Cubic Meter	6597.75220728	47132.692330757
4	<p><b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	4.28625	Cubic Meter	8178.92408236	35056.913348016

5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	8.4825	Square Meter	216.23489289764	1834.2124790042
---	--	--------	--------------	-----------------	-----------------

<b>Total Amount:</b>	85834.446949516
----------------------	-----------------

Provision for Contingency (+) @	886
Display Citizen Board (+) @	1860
Any Other Lumpsum (+) @	

<b>Total Amount:</b>	88580.446949516
----------------------	-----------------

<b>Grand Net Total Amount</b>	88580.446949516
-------------------------------	-----------------

**Dipti Ranjan Mohanty**  
**JE**  
**Jagatsinghpur Block**

**Sri Susanta Kumar Rout**  
**AEE**  
**Jagatsinghpur Block**

**Sri Ashutosh Mishra**  
**BDO**  
**Jagatsinghpur Block**