

**Estimate Abstract**

**OD/345/3294/115962/420152/00016246 : Improvement Of Road From NH To Kandagarh  
Block : Puintala, Gram Panchayat : Bairasar  
Created By: BIBHUTI BHUSAN MOHANTY**

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<p><b>Road Work : AR1308 (moorum and sand admixture laying in sub-base in layers not exceeding 100mm watering and compacting to the required density in O.M.C with PRR)</b> : Supplying &amp; spreading moorum and sand admixture in a ratio (70:30) laying in sub-base in layers not exceeding 100mm watering and compacting to the required density in O.M.C with PRR including cost, conveyance, royalty, taxes cost of all labour &amp; material, hire charges of T &amp; P materials required for work as per specification and complete as per direction of Engineer-in-Charge.</p>	212.376	Cubic Meter	1130.7691541643	240148.2298848

<b>Total Amount:</b>	240148.2298848
----------------------	----------------

Provision for Contingency (+) @	2401.482298848
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	4450
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	249999.71218365
----------------------	-----------------

<b>Grand Net Total Amount</b>	249999.71218365
-------------------------------	-----------------

**BIBHUTI BHUSAN MOHANTY**  
**JE**  
**Puintala Block**

**PRIYAMBADA KALO**  
**AEE**  
**Puintala Block**

**AMARENDRA SWAIN**  
**BDO**  
**Puintala Block**