

Estimate Abstract

OD/359/3430/118983/415424/00013535 : Const. of CC road with Guard wall from Badebali to Tadri

Block : Phulbani, Gram Panchayat : Jamjhari

Created By:ANANDA KUMAR MEHER

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	12.74256	Cubic Meter	235.56432	3001.6924814592
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	11.27291808	Cubic Meter	674.101472	7599.0906714634

3	<p>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	29.13515552	Cubic Meter	5399.7895024	157323.70692769
4	<p>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	13.7088708	Cubic Meter	8089.9556508	110904.15679455

5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	60.8607553	Square Meter	215.69813962884	13127.551694616
6	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	10.56771625	Square Meter	190.432112864	2012.4325336347

Total Amount:	293968.63110341
----------------------	-----------------

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	

Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	3031

Total Amount:	299999.63110341
----------------------	-----------------

Grand Net Total Amount	299999.63110341
-------------------------------	-----------------

ANANDA KUMAR MEHER
JE
Phulbani Block

Bishnu Prasad Khadanga
AEE
Phulbani Block

SOUMYA RANJAN PATRO
BDO
Phulbani Block