

Estimate Abstract

OD/366/3517/120497/427967/00016376 : Const. of Culvert From Majhiguda to Masanipaada
Road

Block : Nabarangpur, Gram Panchayat : Sindhigam

Created By:S K MURSHID

Sl No	Description of work	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	19.875	Cubic Meter	240.77592	4785.42141
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	8.7075	Cubic Meter	515.507232	4488.77922264

3	<p>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	8.7075	Cubic Meter	5279.21385208	45968.754616987
4	<p>R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	10.3725	Cubic Meter	5578.1579568616	57859.443407547

5	<p>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	31.2	Square Meter	216.39264180804	6751.4504244108
6	<p>R.C.C. Work : AR0410a (Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	11.25	Square Meter	663.29946175911	7462.11894479

7	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	4	Quintal	10418.6245485	41674.498194
8	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	5.376	Cubic Meter	6846.25691796	36805.477190953

Total Amount:	205795.94341133
----------------------	-----------------

Provision for Contingency (+) @	1204
Display Citizen Board (+) @	3000

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	209999.94341133
----------------------	-----------------

Grand Net Total Amount	209999.94341133
-------------------------------	-----------------

S K MURSHID
JE
Nabarangpur Block

SURYA NARAYAN BEHERA
AEE
Nabarangpur Block

SUNIL KHORA
BDO
Nabarangpur Block