

Estimate Abstract

**OD/356/3394/118246/401861/00022123 : Imp of Road with CC/ Gr-II Metalling from Jitendra Mohapatra House to Hursikesh Pradhan House
Block : Badchana, Gram Panchayat : Bharatpur
Created By: Biplab Parija**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.975	Cubic Meter	240.77592	957.084282
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.6	Cubic Meter	1055.503732	2744.3097032
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.65	Cubic Meter	6367.75284386	16874.545036229
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	20.1	Cubic Meter	7911.46825082	159020.51184148
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	12	Square Meter	216.23489289764	2594.8187147717

Total Amount:	182191.26957768
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	2340.73

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	186531.99957768
----------------------	-----------------

Grand Net Total Amount	186531.99957768
-------------------------------	-----------------

Biplab Parija
JE
Badchana Block

Parthasarathi Panda
AEE
Badchana Block

Rabindra Kumar Pradhan
BDO
Badchana Block