

Estimate Abstract

**OD/345/3285/115797/420271/00016232 : Const Of CC Road At PWD Road To Talibandh
Block : Balangir, Gram Panchayat : Sibtala
Created By:Jyotranjan Mohanty**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	22.2570048	Cubic Meter	240.77592	5358.9508071644
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.2449312	Cubic Meter	620.648232	10703.036060242
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.40592	Cubic Meter	5438.43082576	100099.32270447
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	9.061376	Cubic Meter	7001.38556112	63442.187090279
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	65.0321	Square Meter	216.39264180804	14072.467921325

Total Amount:	193675.96458348
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	3000

Any Other Lumpsum (+) @	1324
Provision for survey investigation and quality control (+) @	
Total Amount:	199999.96458348
Grand Net Total Amount	199999.96458348

Jyotranjan Mohanty
JE
Balangir Block

Neincy Rani Purty
AEE
Balangir Block

HRUSHIKESH GOND
BDO
Balangir Block