

Estimate Abstract

**OD/344/3282/115734/403679/00018080 : Const of CC Road Of Kansar Village Road
Block : Palalahada, Gram Panchayat : Rohila
Created By:MAHESWAR BEHERA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	7.6237018216576	Cubic Meter	240.77592	1835.6038199153
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.902383333229	Cubic Meter	1386.985732	26217.335983983
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.575564784858	Cubic Meter	6027.54205218	178267.96045771
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	21.9518629632	Cubic Meter	7497.32743066	164580.30434809
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	84.060120848	Square Meter	216.23489289764	18176.73122853

Total Amount:	389077.93583822
----------------------	-----------------

Provision for Contingency (+) @	3890.7793583822
Display Citizen Board (+) @	3140.5

Any Other Lumpsum (+) @	3890.7793583822
Provision for survey investigation and quality control (+) @	
Total Amount:	399999.99455499
Grand Net Total Amount	399999.99455498

MAHESWAR BEHERA
JE
Palalahada Block

PRAMOD KUMAR SWAIN
AEE
Palalahada Block

NISHAN MISHRA
BDO
Palalahada Block