

Estimate Abstract

**OD/347/3312/116387/380609/00014382 : Compl of CC at Karnatikra
Block : Bargarh, Gram Panchayat : Kuruan
Created By:SUDHIR KUMAR NATH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.6	Cubic Meter	5395.36118972	51795.467421312
2	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	96	Square Meter	1010.4678118202	97004.909934739
3	Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	15.54	Square Meter	1532.810532607	23819.875676713
4	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	121.725	Square Meter	244.987551724	29821.109733604
5	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	122.4	Square Meter	190.3880380396	23303.495856047
6	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	155.4	Square Meter	170.5865895744	26509.156019862

7	Other Building Items. : AR1902 (cement based wall putty (water based)) : Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.			
	244.125	Square Meter	79.21834	19339.1772525
8	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	244.125	Square Meter	71.67920296271	17498.685423272
9	Painting : AR0922 (Finishing wall two coats with distemper of approved shades on new work (Inside)) : Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	244.125	Square Meter	78.85653275	19250.851057594
10	Painting : AR0918ca (Finishing wall two coats with weather coat with one coat oilbound Primer) : Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	155.4	Square Meter	156.87106423771	24377.76338254

Total Amount:	332720.49175818
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	80000
Provision for Contingency (+) @	3279.5
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	79000
Provision for survey investigation and quality control (+) @	

Total Amount:	499999.99175818
----------------------	-----------------

Grand Net Total Amount	499999.99175818
-------------------------------	-----------------

SUDHIR KUMAR NATH
JE
Bargarh Block

SANTOSH KUMAR BEHERA
AEE
Bargarh Block

BERCIUS DUNGUNG
BDO
Bargarh Block