

Estimate Abstract

**OD/345/3296/116023/421532/00062845 : IMPROVEMENT OF ROAD FROM KALIMANDIR TO JORE ROAD
Block : Titlagarh, Gram Panchayat : Sihini
Created By:HAREKRUSHNA DASH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.165	Cubic Meter	240.77592	1484.3835468
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.231875	Cubic Meter	465.007232	11267.99711992
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	31.1675	Cubic Meter	4851.41368486	151206.43602287
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	18.751875	Cubic Meter	6558.68132082	122987.57229285
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	27.4	Square Meter	216.23489289764	5924.8360653953

Total Amount:	292871.22504784
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	3000

Any Other Lumpsum (+) @	1128
Provision for survey investigation and quality control (+) @	
Total Amount:	299999.22504784
Grand Net Total Amount	299999.22504784

HAREKRUSHNA DASH
JE
Titlagarh Block

ANSHU KUMAR
AEE
Titlagarh Block

CHANDRAMANI NAG
BDO
Titlagarh Block