

**Estimate Abstract**

**OD/346/3309/116317/393979/00063520 : Repair and restoration of Kedarpur -4 AWC  
Block : Soro, Gram Panchayat : Kedarpur  
Created By:Monalisa Pati**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.102	Cubic Meter	240.77592	746.88690384
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.0123	Cubic Meter	1493.995232	5994.3570693536
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	6.2272	Cubic Meter	6090.04545374	37923.93104953
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	25.68	Square Meter	216.32323228746	5555.180605142
5	<b>Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) :</b> Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	47.247	Square Meter	1531.949359036	72380.011366374
6	<b>Painting : AR0919 (Finishing wall One Coat with plastic emulsion paint of approved shades on old work (Inside)) :</b> Finishing wall One Coat with plastic emulsion paint of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	171.81	Square Meter	61.2232611525	10518.768498611

7	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	4.815	Cubic Meter	7138.83386138	34373.485042545
8	<b>Painting : AR0901b (Priming one coat in inner surface with primer of approved quality over iron work.) :</b> Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	24.07	Square Meter	66.11573166851	1591.405661261
9	<b>Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) :</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	262.622	Square Meter	71.83248932951	18864.792012695
10	<b>Painting : AR0918ca (Finishing wall two coats with weather coat with one coat oilbound Primer) :</b> Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	50.82	Square Meter	156.85349521701	7971.2946269284
11	<b>Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) :</b> Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	13.5	Square Meter	230.34345832053	3109.6366873272

<b>Total Amount:</b>	199029.74952361
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	770.25
Display Citizen Board (+) @	200
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	199999.99952361
----------------------	-----------------

<b>Grand Net Total Amount</b>	199999.99952361
-------------------------------	-----------------

**Monalisa Pati**  
**JE**  
**Soro Block**

**Nirmala Kanta Parida**  
**AEE**  
**Soro Block**

**Satyanath Naik**  
**BDO**  
**Soro Block**