

Estimate Abstract

**OD/370/3553/121204/426332/00063443 : Construction of CC Road at Bandhaguda of Mukundpur GP-
Block : Kolnara, Gram Panchayat : Mukundapur
Created By:GOURISHYAM NAIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	66.76867	Cubic Meter	240.77592	16076.287946426
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.93535	Cubic Meter	825.880232	11508.930091001
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.22367	Cubic Meter	5283.35209074	96282.064995456
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	10.4025	Cubic Meter	6779.04570238	70519.022919008
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	16.66	Square Meter	216.23489289764	3602.4733156747

Total Amount:	197988.77926757
----------------------	-----------------

Provision for Contingency (+) @	1979.8877926757
Display Citizen Board (+) @	31

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.66706024
----------------------	-----------------

Grand Net Total Amount	199999.66706025
-------------------------------	-----------------

GOURISHYAM NAIK
JE
Kolnara Block

SAMEER KUMAR RATHA
AEE
Kolnara Block

SMT REENA PRADHAN
BDO
Kolnara Block